

Tender Inviting Authority: SuperIntending Engineer, EUDC-II, Ghaziabad (U.P.)

Names of Work: विद्युत नगरीय वितरण सफ्ट-वर्क, गाजियाबाद के कार्सेन में त्रिज विहार, कड़कड़ व अम्बिका नाला पुलिया पर सेतु निर्माण में बाधक 33 कोषी एवं 11 कोषी लाईनों को पूर्ण जमा योजना में वाहय एजेन्सी के माध्यम से शिफ्ट करना व अन्य कार्य।

Contract No: 0120 2607114

PRICE SCHEDULE FOR RE-TENDER NO-09/W/2024-25/EUDD-6/GZB									
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable									
Sl. No.	Item Description	NUMBER	TEXT	TEXT #	NUMBER #	NUMBER #	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1		3	4	5	6	7			8
1.00	विद्युत लगीय विद्युत लाइन-बटन, सावधानता के कारखाने में बिज विद्युत, कड़कट व अधिकता नाता पुलिसा पर सेतु निर्माण में बाक 33 केरी एवं 11 केरी लाईनी को पूर्ण बना लेखना में बाह्य एक्सीटी के मायम से शिफ्ट कराना व अन्य कार्य।								
1.01	Safe Carriage HT 11 KV XLPE Cable 3x185 Sq.mm from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	1700	Mtr.	INR		0.00	INR Zero Only		
1.02	Safe Carriage HT 33 KV XLPE Cable 3x300 Sq.mm from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	1785	Mtr.	INR		0.00	INR Zero Only		
1.03	Safe Carriage 08 No. Steel Tubler Pole SP-55 11 Meter and 12 No. SP-72 13 Meter from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	20	No.	INR		0.00	INR Zero Only		
1.04	Safe Carriage of line accessories such as 36 Meter ACSR Dog Conductor, 24 No. 11 KV Polymeric PIN Insulator, 12 No. 11 KV Disc Insulator, 06 No. Disc fittings., 18 No. 33 KV Polymeric PIN Insulator, 190 Kg. Stay GI Wire 7/8 SWQ, 04 No. Stay Set (16x1800 mm), 26 No. Stay Rod Complete 20 mm 08 No. Earthing Rod (254x20mm) and 84 Meter GI Pipe 6" dia from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only		
1.05	Safe Carriage of 11 KV XLPE Straight Through Cable Box 3x185 Sq.mm from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both and work of Filling/Installation the same as per RESPO.	4	No.	INR		0.00	INR Zero Only		
1.06	Safe Carriage of 33 KV XLPE Straight Through Cable Box 3x300 Sq.mm from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both and work of Filling/Installation the same as per RESPO.	4	No.	INR		0.00	INR Zero Only		
1.07	Safe Carriage of 11 KV XLPE Outdoor Cable Box 3x185 Sq.mm from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both and work of Filling/Installation the same as per RESPO.	8	No.	INR		0.00	INR Zero Only		
1.08	Safe Carriage of 33 KV XLPE Outdoor Cable Box 3x300 Sq.mm from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both and work of Filling/Installation the same as per RESPO.	28	No.	INR		0.00	INR Zero Only		
1.09	Laying of 11 KV HT Cable of 3x185 Sq.mm Drilling of dia 160 mm in two parallel bores by trenchless method by horizontal boring and depth 1.5 to 2 m below ground level in hot mixed rod with HDPE Pipe 160 mm dia.	1500	Mtr.	INR		0.00	INR Zero Only		
2.00	Laying of 33 KV HT Cable of 3x300 Sq.mm Drilling of dia 160 mm in two parallel bores by trenchless method by horizontal boring and depth 1.5 to 2 m below ground level in hot mixed rod with HDPE Pipe 160 mm dia.	1860	Mtr.	INR		0.00	INR Zero Only		
2.01	Erection of Steel Tubler Pole 11/13 meter as per RESPO specification.	20	No.	INR		0.00	INR Zero Only		
2.02	Concreting/Grouting of Poles	8	No.	INR		0.00	INR Zero Only		
2.03	Earthing of Pole as per RESPO specification.	8	No.	INR		0.00	INR Zero Only		
2.04	PROVIDING and FIXING of Nutt & Bolts with Washer.	466	Kg.	INR		0.00	INR Zero Only		
2.05	PROVIDING and FIXING Pole Clamp with Nut & Bolts.	174	No.	INR		0.00	INR Zero Only		
2.06	PROVIDING and FIXING M5 Angle 75x75x6 mm.	220	Kg.	INR		0.00	INR Zero Only		
2.07	PROVIDING and FIXING M5 Channel 100x50x5 mm.	400	Kg.	INR		0.00	INR Zero Only		
2.08	PROVIDING and FIXING M5 Channel 125x65x5 mm.	900	Kg.	INR		0.00	INR Zero Only		
2.09	PROVIDING and FIXING Danger Board with Clamp.	7	No.	INR		0.00	INR Zero Only		
3.00	Carriage of old & used material from site to Store Sahibabad/ Ghaziabad/ Noida including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only		
Total In Figures						0.00	INR Zero Only		
Quoted Rate in Words						INR Zero Only			