

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण खण्ड-बस्टम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 (पार्ट-2) मद में 11 के0वी0 लाईन निर्माण एवं बाइफरकेशन आदि के कार्य हेतु।

Contract No: 9193320600

Name of the Bidder/							
<div>PRICE SCHEDULE FOR E-TENDER NO-21/W/2024-25/EUDD-VI/EUDC-2/GZB</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only ) GST EXTRA as applicable</div>							
NUMBER	TEXT #	NUMBE	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय वितरण खण्ड-बस्टम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 (पार्ट-2) मद में 11 के0वी0 लाईन निर्माण एवं बाइफरकेशन आदि के कार्य हेतु।						
1.01	Safe Cartage of ST Pole 11 Mtrs. Long from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	36	No.	INR		0.00	INR Zero Only
1.02	Carriage of 11 KV HT Cable 3x185 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	5040	Mtr.	INR		0.00	INR Zero Only
1.03	Carriage of 56 No.11 KV Outdoor Cable Box of 3x185 Sq.mm. and 1700 meter ACSR Dog Conductor. PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only
1.04	Carriage of material such as 4150 meter Cable Tranchless with HDPE Pipe O/D 140mm. and 30 No. 11 KV Disc Insulator, 132 No. 11 KV Pin Insulator from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only
1.05	Installation/Fixing of Outdoor Cable Box 11 KV 3x185 Sq.mm	56	No.	INR		0.00	INR Zero Only
1.06	Erection, Grouting, Concreting & Installation of Double Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	10	No.	INR		0.00	INR Zero Only
1.07	Erection, Grouting, Concreting & Installation of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	26	No.	INR		0.00	INR Zero Only
1.08	Work of Concreting/Grouting of Pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	26	No.	INR		0.00	INR Zero Only
1.09	Laying/Erection of ACSR Dog Conductor. Proper completion of work as per requirement of site.	1700	Mtr.	INR		0.00	INR Zero Only
2.00	Laying of 11 KV HT Cable of 3x185 Sq.mm with Trenchless method by providing of HDPE Pipe and proper completion of work as per requirement of site.	4150	Mtr.	INR		0.00	INR Zero Only
2.01	Normal Laying of 11 KV HT Cable of 3x185 Sq.mm. Proper completion of work as per requirement of site.	5040	Mtr.	INR		0.00	INR Zero Only
2.02	Earthing of pole by providing Earth Rod (2540x20mm)	36	No.	INR		0.00	INR Zero Only
2.03	PROVINDING AND FIXING MS Channel 100x50 MM.	1400	Kg.	INR		0.00	INR Zero Only
2.04	PROVINDING AND FIXING Danger Board with Clamp for 11 KV	24	No.	INR		0.00	INR Zero Only
2.05	PROVINDING AND FIXING Number Plate with Clamp for 11 KV	24	No.	INR		0.00	INR Zero Only
2.06	PROVINDING AND FIXING GI Pipe 6 Inch Dia for XLPE Cable.	156	Mtr.	INR		0.00	INR Zero Only
2.07	PROVINDING AND FIXING G.I. Wire 6 SWQ.	45	Kg.	INR		0.00	INR Zero Only
2.08	PROVIDING AND FIXING Nut & Bolt with washer off Size as per RESPO.	55	Kg.	INR		0.00	INR Zero Only
2.09	PROVIDING AND FIXING M.S. Hosding Clamps.	145	No.	INR		0.00	INR Zero Only
3.00	PROVIDING AND FIXING Aluminium Lug 150mm.	144	No.	INR		0.00	INR Zero Only
3.01	PROVIDING AND FIXING M.s. Angle	2	No.	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words			INR Zero Only				