

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण खण्ड-बस्टम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान वर्ष 2024-25 (पार्ट-2) के मद में 11/0.4 के0वी0 उपकेन्द्रों का निर्माण आदि का कार्य ई-निविदा द्वारा बाह्य एजेन्सी के माध्यम से कराने के सम्बन्ध में।

Contract No: 9193320600

Name of the Bidder/ Biddin							
<div>PRICE SCHEDULE FOR E-TENDER NO-19/W/2024-25/EUDD-6/EUDC-2/GZB</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable</div>							
NUMB	TEXT #	NUMBE	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय वितरण खण्ड-बस्टम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान वर्ष 2024-25 (पार्ट-2) के मद में 11/0.4 के0वी0 उपकेन्द्रों का निर्माण आदि का कार्य ई-निविदा द्वारा बाह्य एजेन्सी के माध्यम से कराने के सम्बन्ध में।						
1.01	Construction of plinth of size 2MX2MX1.5M above ground level and one ft. below the ground level of 9". After excavation of 4" earth, brick ballast shall be provided and rammering will be done properly after that a retaining wall of 9" width by first class brick in ratio 1:4 of cement and sand shall be made. The earth shall be filled upto one ft. below the top of the plinth. After this brick ballast shall be provided upto 6" from the earth level and proper rammering shall be done. One no. jaal of 12mm MS Tor shall be fixed in the hollow of the plinth and one ft. thick RCC in 1:2:4 ratio of cement , sand and stone ballast shall be laid on the top of the plinth. The 12mm thick plastering shall be done all around the plinth in ratio 1:4 ratio of cement and sand. The contractor shall be responsible to complete the work as per direction of supervising Engineer. It includes the cost of labour, T&P, carrier etc. required for proper completion of the work (This material will be provided by the Contactor).	5	No.	INR		0.00	INR Zero Only
1.02	Fabrication of wire mesh fencing frames of different size fabricate out of MS angle iron of size 3x3x2M. Each frame duly welded and fixing with wire mesh of size 25x25x10 SWG hot dipped galvanized within the frame pressed under MS flats of size 40x5mm inside the angle on all four side with help of approx. 20No. Bolts & Nuts of 10mm diameter 45cm legs of frame will be grouted in 1:2:4 cement coarse sand and 20mm gauge stone blast in the size of 0.22x0.22x0.45meter. Each will be painted with one coat of red oxide and two coat of Alluminium paint of approved mark after proper cleaning. Fixing of wire mess fencing around on plinth of T/F with wire gauge 25x25mm, MS Angle 35x35x5mm with gate.	5	No.	INR		0.00	INR Zero Only
1.03	Safe Carrige of 250 KVA Transformer from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Installation of TF at plinth including all accessories. Complete work as per requirement of site/RESPO norms.	5	No.	INR		0.00	INR Zero Only
1.04	Safe Carrige of ST Pole 11 Meter long from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Erection/Installation of poles including all accessories. Complete work as per requirement of site.	9	No.	INR		0.00	INR Zero Only
1.05	Safe Carrige of 01 No. PCC Pole 8.5 Meter long and 5 No. PCC Pole 09 Meter long from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Erection/Installation of poles including all accessories. Complete work as per requirement of site.	6	No.	INR		0.00	INR Zero Only
1.06	Safe Carriage of ABC Cable 3x120+1x95+1x16 Sq.mm Cable from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, stringing, binding, sagging & jumpering etc. Complete the work as per requirement of site/RESPO norms.	363	Mtr.	INR		0.00	INR Zero Only

1.07	Safe Carriage of 260 Meter LT XLPE 1x240 Sq.mm Cable from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, stringing, binding, sagging & jumpering etc. Complete work as per requirement of site/RESPO norms.	260	Mtr.	INR		0.00	INR Zero Only
1.08	Safe Carriage of 27 No. 11 KV Composite Polymeric Pin Insulator from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end.	27	No.	INR		0.00	INR Zero Only
1.09	Safe Carriage of 250 Meter ACSR Weasel Conductor and 09 No. Earth Rod Size (2540x20) from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, Sagging, Stringing, Binding & Jumpering etc. Complete the work as per RESPO norms and requirement of site.	259	Mtr.	INR		0.00	INR Zero Only
2.00	Work of Chemical Earthing by providing all the required material for completion of work. Complete the work as per RESPO norms.	10	No.	INR		0.00	INR Zero Only
2.01	Work of Earthing of pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	6	No.	INR		0.00	INR Zero Only
2.02	Providing and fixing of Sundary Items A) MS Clamp for STP	68	No.	INR		0.00	INR Zero Only
2.03	Providing and fixing of Sundary Items A) Top Channel Size 100x50x2x2240	6	Kg.	INR		0.00	INR Zero Only
2.04	Providing and fixing of Sundary Items A) G.I. Droper Channel Size 100x50x2028	6	No.	INR		0.00	INR Zero Only
2.05	Providing and fixing of Sundary Items A) G.I. Droper Channel Size 100x50x2000	2	Kg.	INR		0.00	INR Zero Only
2.06	Providing and fixing of Sundary Items A) D.O. 11 KV Fuse Set	5	No.	INR		0.00	INR Zero Only
2.07	Providing and fixing of Sundary Items A) Pearcing Clamps.	8	No.	INR		0.00	INR Zero Only
2.08	Providing and fixing of Sundary Items A) Suspension Clamp with I-Hook.	12	No.	INR		0.00	INR Zero Only
2.09	Providing and fixing of Sundary Items A) Dead End Clamp with I-Hookk.	9	No.	INR		0.00	INR Zero Only
3.00	Providing and fixing of Sundary Items A) Bracing Clamp with nut & bolt	4	No.	INR		0.00	INR Zero Only
3.01	Providing and fixing of Sundary Items A) Nutt & Bolts with Washer.	9	Kg.	INR		0.00	INR Zero Only
3.02	Providing and fixing of Sundary Items A) All. Crimping Lug 1x240 Sq. mm.	28	No.	INR		0.00	INR Zero Only
3.03	Providing and fixing of Sundary Items A) Danger Board 11 KV With clamp	3	No.	INR		0.00	INR Zero Only
3.04	Providing and fixing of Sundary Items A) MS Angle Size 65x65x6 mm 2700mm.	80	No.	INR		0.00	INR Zero Only
3.05	Providing and fixing of Sundary Items A) 3 Phase Distribution Box.	2	No.	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					