

[Validate](#)[Print](#)[Help](#)**Item Rate BoQ**

Tender Inviting Authority: Superintending Engineer, Electricity Distribution Circle-II Meerut.

**Name of Work:** REGARDING FOR THE WORK OF DUE TO BREAK DOWN REPLACEMENT OF BURNT AND DAMAGED 11 KV EPOXY RESIN CAST CT'S AND COMPLETE REPAIRING OF 11 KV DIFFERENT MAKE PANEL AT VARIOUS 33/11 KV SUB-STATIONS UNDER THE JURISDICTION OF EDD-1 MAWANA.

Contract No: 9193301001

Name of the Bidder/ Bidding Firm / Company :						
<b>TENDER NO. 171/EDC-2/MT/2023-24 PRICE SCHEDULE</b>						
<b>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</b>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	REGARDING FOR THE WORK OF DUE TO BREAK DOWN REPLACEMENT OF BURNT AND DAMAGED 11 KV EPOXY RESIN CAST CT'S AND COMPLETE REPAIRING OF 11 KV DIFFERENT MAKE PANEL AT VARIOUS 33/11 KV SUB-STATIONS UNDER THE JURISDICTION OF EDD-1 MAWANA. .					
1.01	The following woks attending breakdown for replacement of burnt and damaged 11 KV EPOXY resin cast CT'S and complete repairing of 11 KV different make panel at various 33/11 KV SUB-STATIONS UNDER THE JURISDICTION OF EDD-1 MAWANA. 1. Opening of cable box after scraping of insulation & cutting of burnt/Rusted nuts & bolts etc. 2. Opening & re-fixing of main bus –bars with the help of nuts & bolts after removing carbon by amri clothes & CTC & re-insulation of 3 phase of bus bars of HT & Empire Tape etc. 3. Opening & re-fixing of spout sets & epoxy resin cast CTs after remove carbon by CTC & if damaged will be replaced provided by the department. 4. Re-insulation of all joints of spouts after remove carbon by CTC and insulation by HT & Empire tape. 5. Fixing of cable box in CT side with the help of nuts & bolts & Washers & insulation of each of cable box by HT & Empire Tape etc. Note:- The repair works shall be involved in carrying out the repair works Panels. The items/Parts (damage/unserviceable) shall be provided by the department for replacement of the same.	12	Nos.		0.00	INR Zero Only
1.02	Providing of 11 KV Epoxy Resin caste CT of Ratio 600/300/5 Amps. of 11 KV different make 11 KV Switchgears.	6	Nos.		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				