

Inviting Authority: Superintending Engineer Electricity Civil Distribution Circle, PVVNL, Meerut.
 Name of Work: Special Repair of Related Civil work of Sub-Division Office at Electricity Distribution Sub-Division-IInd, Partapur, Meerut.
 T.S. No: 28/ECDC/MRT/2021-22

Name of the
Bidder/
Firm/
Company:

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT In Rs. P	TOTAL AMOUNT In Words
1	Excavation in foundation in ordinary soil (loam, clay or sand) including lift upto 1.5 Metre and lead upto 30 metre including filling, watering, and ramming of excavated earth into the trenches or into the space between the building and the side of the foundation or in to the plinth and removal & disposal of surplus earth as directed by the E/I up to a distance of 30m from the foundation trenches. CSI No. 4.01	40.00	Cum	172.00	6880.00	INR Six Thousand Eight Hundred & Eighty Only
2	Concrete with 4cm gauge stone ballast, coarse sand (F.M. 1.8 to 2.5) & cement in proportion of 12:6:1 in foundations & under floors including supply of all materials, labour and tools and plants etc. required for proper completion. CSI No. 5.02	0.85	Cum	4971.00	4225.35	INR Four Thousand Two Hundred & Twenty Five and Paise Thirty Five Only
3	Cement concrete with 2cm gauge approved hard stone ballast, coarse sand (F.M. 1.8 to 2.5) and cement in proportion of 4:2:1 including supply of all materials, labour, side shuttering if required and T&P etc. required for proper completion of work. CSI No. 5.06	3.80	Cum	6520.00	24776.00	INR Twenty Four Thousand Seven Hundred & Seventy Six Only
4	Precast cement concrete door sills, chaukhats boundary posts, shelves and similar small work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast in the proportion 1:2:4, excluding reinforcement but including fixing the same in position including cost of all other material, labor and T&P. CSI No. 5.09	0.50	Cum	7970.00	3985.00	INR Three Thousand Nine Hundred & Eighty Five Only
5	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:1.5:3 in lintels of doors and windows, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.23	0.10	Cum	8058.00	805.80	INR Eight Hundred & Five and Paise Eighty Only
6	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:1.5:3 in lintels of doors and windows, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.24	0.50	Cum	9275.00	4637.50	INR Four Thousand Six Hundred & Thirty Seven and Paise Fifty Only
7	1st class brick (not less than class 150) work in 1:6 C.M. with cement and coarse sand (2.9 to 3.2 F.M) mortar in foundation and plinth including supply of all material, labour and T&P etc. required for proper completion of work. CSI No. 6.01	5.20	Cum	4518.00	23493.60	INR Twenty Three Thousand Four Hundred & Ninety Three and Paise Sixty Only
8	1st class brick work in 1:6 C.M. with cement and coarse sand of 2.25 F.M. mortar in super structure including necessary cutting and moulding of brick as required including honey comb brick work, thickness of wall one brick (230mm) thick in super structure. CSI No. 6.01+6.08	4.80	Cum	4820.00	23136.00	INR Twenty Three Thousand One Hundred & Thirty Six Only
9	Same as item no. 08 above but for wall of half brick 4.5" (115 mm) thick but in 1:6 C.M. with cement and coarse sand of 2.25 F.M. mortar. CSI No. 6.01+6.09	0.70	Cum	4971.00	3479.70	INR Three Thousand Four Hundred & Seventy Nine and Paise
10	Brick work in foundation & plinth with old dismantled bricks (supplied by department free of cost) and coarse sand of F.M. 1.8 to 2.5 mortar in 1:6 including supply of all other materials, labour, removing mortar & cleaning of old & used bricks, T&P etc complete. CSI No. 6.18	1.50	Cum	2572.00	3858.00	INR Three Thousand Eight Hundred & Fifty Eight Only
11	Supply and fixing Stainless Steel mosquito proof heavy quality iron wire mesh of 15x28 G over windows and including supply of Shisham wood battens (40x15) mm size and including supply and fixing of necessary screws all materials, labour and T&P etc. required for proper completion of the work. CSI No. 8.43	31.50	Sqm	1058.00	33327.00	INR Thirty Three Thousand Three Hundred & Twenty Seven Only
12	Supply and fixing of 32 mm thick single leaf flush door shutter (boiled water resistance, phenol maldehyde resin bonded, hot pressed factory made) commercial quality to I.S.2202 part-1 (1983) ISI marked including fixing of wooden cleats and stoppers and including fixing and adjustment of hinges, bolts, locks, handles, springs and other fittings but excluding their supply including all materials, labour & T&P etc. required for proper completion of work. CSI No. 8.57	2.00	Sqm	1915.00	3830.00	INR Three Thousand Eight Hundred & Thirty Only

J.E

SDO-I

A.E

E.E

	Mild Steel or Iron work in heavy sizes such as trusses built up, gates, door frames, record racks roof work gates etc. wrought to required form including holes riveting or welding where necessary and also fixing in proper position and alignment including cost of all materials supplied by contractor. CSI No. 9.01	0.70	M.T.	83076.00	88183.20	INR Fifty Eight Thousand One Hundred & Fifty Three and Paise Twenty Only
14	3M1/Tor steel in plain work such as reinforced concrete or reinforced brick work (when not included in an over all rates) wrought to required shape as necessary including bending for proper completion of the work and including supply of steel its wastage, bend, hooks and authorized overlapping shall be measured. (Steel shall be arranged by the contractor) CSI No. 9.03	0.10	M.T.	74620.00	7462.00	INR Seven Thousand Four Hundred & Sixty Two Only
15	Supply and laying water proof craft paper in double layer with grease, including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 10.09	10.00	Sqm	151.00	1510.00	INR One Thousand Five Hundred & Ten Only
16	Supply and painting of 85/25 grade bitumen paint over roof @ 1.7 Kg/ sq m and spreading 6 mm size gnt over it @ 1 cft/100 Sq Ft. including sweeping, cleaning the roof with brush, heating the paint to required temperature and supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 10.12	10.00	Sqm	204.00	2040.00	INR Two Thousand & Forty Only
17	12 mm thick plaster with cement mortar consisting of one part of cement & three part of coarse sand (1:3), minimum thickness not to be less than 10 mm including supply of all material, labour and T&P etc for proper completion of work. CSI No. 11.06	20.00	Sqm	194.00	17460.00	INR Seventeen Thousand Four Hundred & Sixty Only
18	Same as item No. 17 above but with 1:6 cement and coarse sand mortar. CSI No. 11.09	70.00	Sqm	169.00	11830.00	INR Eleven Thousand Eight Hundred & Thirty
19	Providing (12x15) mm section groove in plaster including all material, labour and T&P etc. required for proper completion of the work. CSI No. 11.16	75.00	RM	12.00	900.00	INR Nine Hundred Only
20	Making dnp coarse (25x12) mm in 1:2 cement and coarse sand including supply of all materials, labour and T&P etc required for proper completion of work. CSI No. 11.19	35.00	RM	11.00	385.00	INR Three Hundred & Eighty Five Only
21	3 mm thick floating coat of neat cement finish including supply of all materials, labour and T&P etc. required for proper completion of the work. (cement consumption 0.044 bag/Sq m.) CSI No. 11.20	44.00	Sqm	19.00	836.00	INR Eight Hundred & Thirty Six Only
22	40 cm thick 1:2:4 plain cement concrete floor with cement, approved coarse sand & 2cm graded approved stone ballast laid in panels finished with 3mm floating coat of neat cement or cement and marble dust in ratio of 5:1 as specified and removing any overlapping mortar at the joints of the panels if any and giving them a uniform finish including supply of all materials, labour and T&P etc. required for proper completion of the work. without base CC. CSI No. 12.04	3.00	Sqm	386.00	1155.00	INR One Thousand One Hundred & Fifty Eight Only
23	Supply and Laying 8 mm thick glazed floor tiles of Somany, Johnson or equivalent make, laid with 1:3 cement and approved coarse sand mortar finished with white cement slurry, jointing and polishing complete, including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 12.11	159.75	Sqm	1056.00	165696.00	INR One Lakh Sixty Eight Thousand Six Hundred & Ninety Six Only
24	Supply and Laying 6 mm thick glazed tiles in skirting / dado laid with 1:3 cement and approved coarse sand mortar finished with white cement slurry, jointing and polishing complete, including supply of all materials, labour and T&P etc. completion required for proper completion of the work. CSI No. 12.12	18.59	Sqm	719.00	13366.21	INR Thirteen Thousand Three Hundred & Sixty Six and Paise Twenty One Only
25	Providing and fixing glass strips of 3.15 mm thickness & 40mm depth in joints of floor and skirting at the time of laying floors, flush with floor level including supply of all materials, labour & T&P etc. required for proper completion of work. CSI No. 12.14	35.00	RM	31.00	1085.00	INR One Thousand & Eighty Five Only
26	Providing and laying 18 mm thick Kota stone in flooring or skirting over base cement mortar 1:4 mix and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing complete and including supply of all materials labour and T&P etc required for proper completion of the work. CSI No. 12.17	5.00	Sqm	1114.00	5570.00	INR Five Thousand Five Hundred & Seventy Only
27	Painting or varnishing new iron work in small areas or new wood work with one coat of ready mixed priming paint and one coat of approved superior quality ready mix paint "Luxol" or equivalent brand or varnish including supply of all materials, labour and T&P etc. required for proper completion of the work. Paint to be used should conform to the I.S. 103-1950. CSI No. 13.01	10.00	Sqm	71.00	710.00	INR Seven Hundred & Ten Only
28	Same as item No. 27 above but for every coat after 1st coat. CSI No. 13.02	50.00	Sqm	35.00	1050.00	INR One Thousand & Fifty Only
29	Same as item no. 27 above but every coat on previously painted old wood or steel work. CSI No. 13.03	50.00	Sqm	47.00	3760.00	INR Three Thousand Seven Hundred & Sixty Only
30	Applying Birla or equivalent putty on new interior or exterior surface over one coat of water based cement primer of ICI or equivalent brand for smoothening and levelling of the surface as per requirement and direction of Engineer /C including cost of all material, labour, T & P etc required for proper completion of work. CSI No. 13.20	25.00	Sqm	84.00	2100.00	INR Two Thousand One Hundred Only
31	Applying BIRLA PUTTY or equivalent putty on previously birla putty smoothen surface over one coat of water base cement primer of ICI or equivalent brand for smoothening and levelling of the surface as per requirement and direction of E/I including cost of all material, labour and T&P required for proper completion of work. CSI No. 13.21	556.40	Sqm	41.00	22894.40	INR Twenty Two Thousand Eight Hundred & Ninety Four and Paise Forty Only

J.E

S.D.O-I

A.E

E.E

	Painting one coat with APEX or equivalent brand weather coat paint on previously treated surfaces (well prepared with Birla putty and one coat of primer ICI or equivalent which shall be paid separately) including through washing with water including cost of all materials, labour, T&P required for proper completion of work. CSI No. 13.24	264.60	Sqm	62.00	16405.20	INR Sixteen Thousand Four Hundred & Five and Paise Twenty Only
33	Same as in item no 13.24 above but for every coat of additional APEX or equivalent brand weather coat paint CSI No. 13.23	264.60	Sqm	41.00	10848.60	INR Ten Thousand Eight Hundred & Forty Eight and Paise Sixty Only
34	One priming coat and one coat oil bound distemper on new work including supply of all materials labour and T&P etc. required for proper completion of the work. CSI No. 13.08	50.00	Sqm	65.00	3250.00	INR Three Thousand Two Hundred & Fifty Only
35	Same as item No. 34 above but for every coat after the first coat. CSI No. 13.09	466.48	Sqm	27.00	12594.96	INR Twelve Thousand Five Hundred & Ninety Four and Paise Ninety Six Only
36	Same as item No. 34 above but for every coat on previously old distempered surface. CSI No. 13.10	466.48	Sqm	33.00	15393.84	INR Fifteen Thousand Three Hundred & Ninety Three and Paise Eighty Four Only
37	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by the Engineer-in-charge within a distance of 60 metres. CSI No. 15.01	9.00	Cum	505.00	4545.00	INR Four Thousand Five Hundred & Forty Five Only
38	Dismantling reinforced cement concrete or reinforced brick work, including stacking of dismantled materials as directed by the Engineer-In-charge within a distance of 60 metres. CSI No. 15.03	4.00	Cum	1128.00	4512.00	INR Four Thousand Five Hundred & Twelve Only
39	Dismantling cement concrete or brick or granolithic floors including base concrete and including stacking of dismantled materials as directed by the Engineer In-charge within a distance of 60 metres. CSI No. 15.05	296.65	Sqm	58.00	17205.70	INR Seventeen Thousand Two Hundred & Five and Paise Seventy Only
40	Dismantling doors and windows chowkhats including stacking of materials as directed by Engg-in-Charge within a distance of 60 meters. CSI No. 15.10	2.10	Sqm	69.00	144.90	INR One Hundred & Forty Four and Paise Ninety Only
41	Dismantling existing plaster including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.11	135.00	Sqm	41.00	5535.00	INR Five Thousand Five Hundred & Thirty Five Only
42	Scrapping old white or colour wash or distemper including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.12	731.08	Sqm	13.00	9504.04	INR Nine Thousand Five Hundred & Four and Paise Four Only
43	Supply of 80 mm thick I shaped mechanically compressed inter locking cement concrete paver block manufactured by high pressure & controlled vibration machine having plan dimension 200X(160+120 mm) with minimum 5 mm thick topping of O.P.Cement mixed with 25% marble powder. The compressive strength of concrete pavers blocks shall not be less than 30 MPa & 4.5 Kg/No. including cost of all material, labour, T&P etc. required for proper completion of work as directed by Engineer-in-charge but excluding G.S.T. which shall be paid extra as per rules. CSI No. 12.23	9.00	Sqm	974.00	8766.00	INR Eight Thousand Seven Hundred & Sixty Six Only
44	Boring with 150 mm dia casing pipe to a probable depth of 50m from ground level with skilled and unskilled labour including all T & P boring apparatus supervision charges etc. required for proper completion of the work. CSI No. 18.41 (As per Old Schedule)	60.00	RM	216.00	12960.00	INR Twelve Thousand Nine Hundred & Sixty Only
45	Shrouding and packing coarse sand in between the bore wall and the strainer upto 15m approx. from the bottom of the strainer including cost of all material, labour and T & P etc. required for proper completion of work. CSI No. 18.43 (As per Old Schedule)	0.25	Cum	3000.00	750.00	INR Seven Hundred & Fifty Only
46	Providing 110mm dia Slotted PVC CASING PIPES (Aroma /Supreme) (Pressure 10 Kg / Sqcm.) for making tubewell assembly and cartage to boring site, including cost of all labour, materials and T&P required for assembly making and proper completion of work. CSI No. 19.10 (As per New Schedule)	12.00	RM	578.00	6936.00	INR Six Thousand Nine Hundred & Thirty Six Only
47	Providing 110mm dia Plain PVC CASING PIPES (Aroma /Supreme) (Pressure 10 Kg / Sqcm.) for making tubewell assembly and cartage to boring site, including cost of all labour, materials and T&P required for assembly making and proper completion of work. CSI No. 19.08 (As per New Schedule)	50.00	RM	462.00	23100.00	INR Twenty Three Thousand One Hundred Only
48	Providing and fixing of 110mm dia P.V.C. top or bottem plug/bail of 'Supreme/ Astral' or equivalent make of heavy quality including cost of all materials, labour and T & P etc required for proper completion of work. CSI No. 18.16 (As per Old Schedule)	1.00	Nos	238.00	238.00	INR Two Hundred & Thirty Eight Only
49	Supply & Installation of submersible pump of K.S.B/ CALAMA. or eqt. make including cost of labour, T&P and material required for completion of work. (b) 1.5 HP outlet 40mm dia. or more, Head 71/36, Discharge 2000/6000 LPH. CSI No. 19.32 (b) (As per New Schedule)	1.00	Nos	20466.00	20466.00	INR Twenty Thousand Four Hundred & Sixty Six Only
50	Supply and fixing of submersible cable Havels or equivalent make, for submersible pump complete in all respect. (b) 2.5 mm ² for pump above 1 HP and up to 3 HP. CSI No. 19.33 (b) (As per New Schedule)	60.00	RM	102.00	6120.00	INR Six Thousand One Hundred & Twenty Only
51	Supply and fixing 40mm dia of G.I. ("B" class) column pipes JTC/ JINDAL make with column coupling socket as required for proper completion of work including all labour material & T&P. CSI No. 19.22 (c) (As per New Schedule)	40.00	RM	449.00	17960.00	INR Seventeen Thousand Nine Hundred & Sixty Only

J.E

S.D.O.-I

A.E

B.E


	Supply & installation of electrical control panel of L&T / Havells or equivalent make for submersible pump / pumpset containing contractor relay condenser. (b) for 1.5/ 2 H.P pump set single phase. CSI No. 19.31 (b) (As per New Schedule)	1.00	Nos	5321.00	5321.00	INR Five Thousand Three Hundred & Twenty One Only
		10.00	RM	45.00	450.00	INR Four Hundred & Fifty Only
53	Providing and laying of 25mm dia P.V.C. pipe with special such as tee, sockets etc for laying submersible cable including excavation of trenches (300x300) mm size and back filling of the same etc. required for proper completion of the work. CSI No. 18.18 (As per Old Schedule)	72.00	Per hour	75.00	5400.00	INR Five Thousand Four Hundred Only
54	Testing and developing charges of tubewell for 48 hours or till supply of good discharge of water free from any foreign materials such as silt, sand etc. is obtained by O.P. unit/tractor. CSI No. 18.22 (As per Old Schedule)	1.00	Job	2500.00	2500.00	INR Two Thousand Five Hundred Only
55	Cartage of T & P and boring set by manual boring to and fro from site of work. CSI No. 18.19 (As per Old Schedule)	5.00	Sqm	836.00	4180.00	INR Four Thousand One Hundred & Eighty Only
56	Renewing panes of 4.8 to 5.7 mm glass including supply of glass with putty and brads including supply of all materials, labour and T&P etc. required for proper completion of the work (a) glass of 4 mm thick. CSI No. 20.04 (b)	3.00	Nos	187.00	561.00	INR Five Hundred & Sixty One Only
57	Supply and replacing of following chromium polished iron fittings including cost of nuts, bolts etc. complete. (a) L drops 16 mm dia x 300 long CSI No. 20.17 (a)	3.00	Nos	64.00	192.00	INR One Hundred & Ninety Two Only
58	Same as item No. 57 above but for (c) Tower bolts 10 mm dia x 100 mm long. CSI No. 20.17 (c)	5.00	Nos	77.00	385.00	INR Three Hundred & Eighty Five Only
59	Same as item No. 57 above but for (d) Iron hinges 100 mm size. 12 gauge. thick. CSI No. 20.17 (d)	2.00	Nos	39.00	78.00	INR Seventy Eight Only
60	Same as item No. 57 above but for (f) M.S. handles 100 mm size. CSI No. 20.17 (f)	14.00	Nos	750.00	10500.00	INR Ten Thousand Five Hundred Only
61	Wiring point for light with 1.5 sq. mm. FR PVC insulated multistrand single copper conductor cable in PVC conduit pipe concealed in the wall, 14 SWG copper PVC coated Earth continuity wire, and approved quality, piano type switch ceiling rose/angle/batten holder as per approved sample on 3mm thick phenolic laminated bakelite sheet etc. of matching shade with wall colour complete in all respect. PSI No. 121 (A)	8.00	Nos	852.00	6816.00	INR Six Thousand Eight Hundred & Sixteen Only
62	Wiring point for fan/fresh air fan (light duty exhaust fan) 1.5 sq. mm FR PVC insulated multistrand single core copper conductor cable PVC conduit pipe concealed in the wall, 14 SWG copper earth continuity wire and approved quality, piano type switch & ceiling rose as per approved sample on 3mm thick phenolic laminated bakelite sheet etc. of matching shade with wall colour complete in all respects as per direction of E/I. PSI No. 123 (B)	4.00	Nos	392.00	1568.00	INR One Thousand Five Hundred & Sixty Eight Only
63	Wiring point for plug with 1.5 sq. mm FR PVC insulated multistrand single core copper conductor cable in PVC conduit pipe concealed in the wall 14 SWG copper earth continuity wire and approved quality type switch and socket as per approved sample etc. of matching shade with wall colour complete in all respects as per direction of E/I PSI No. 124 (B)	20.00	RM	190.00	3800.00	INR Three Thousand Eight Hundred Only
64	Providing and fixing 15 mm dia B-class Jindal, JTC, ISI marked G.I. pipes complete with special such as bend, tee, socket, cross, clamp etc earth work including filling the trenches etc required for proper completion of the work. the rate also includes concealed GI fitting where required, cutting and making good the walls etc and all materials, labour and T&P complete. CSI No. 26.01 (a)	10.00	RM	226.00	2260.00	INR Two Thousand Two Hundred & Sixty Only
65	Providing and fixing 20 mm dia B-class Jindal, JTC, ISI marked G.I. pipes complete with special such as bend, tee, socket, cross, clamp etc earth work including filling the trenches etc required for proper completion of the work. the rate also includes concealed GI fitting where required, cutting and making good the walls etc and all materials, labour and T&P complete. CSI No. 26.01 (b)	2.00	Nos	451.00	902.00	INR Nine Hundred & Two Only
66	Providing and fixing full way 15mm dia G.M. gate valve with wheel, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.04 (a)	2.00	Nos	631.00	1262.00	INR One Thousand Two Hundred & Sixty Two Only
67	Providing and fixing full way 20mm dia G.M. gate valve with wheel, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.04 (b)	2.00	Nos	242.00	484.00	INR Four Hundred & Eighty Four Only
68	Providing and fixing PVC BALL FLOAT VALVE 15 mm dia. WITH BRASS & UNION COMPLETE, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.06 (a)	4.00	Nos	131.00	524.00	INR Five Hundred & Twenty Four Only
69	Providing and fixing PVC CONNECTION PIPE, 450X15 with 2 brass units ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.09 (b)	5.00	Nos	102.00	510.00	INR Five Hundred & Ten Only
70	P/F GI UNIONS NOMINAL BORE 15 mm, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.10 (a)	6.00	Nos	120.00	720.00	INR Seven Hundred & Twenty Only
71	P/F GI UNIONS NOMINAL BORE 20 mm, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.10 (b)	1000.00	Lit	11.00	11000.00	INR Eleven Thousand Only
72	Supply and fixing of Syntex or equivalent make water storage tank including all materials, labours, T&P etc required for proper completion of work. CSI No. 26.12					


J.E

Japal
S.D.O-ICh
A.E


E.E

	Providing and fixing CP BRASS BIB COCK 15 mm dia. HEAVY QUALITY (400gm) (L & K and equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16(a)	5.00	Nos	660.00	3300.00	INR Three Thousand Three Hundred Only
74	Providing and fixing C.P. BRASS telephonic shower HEAVY QUALITY (L & K and equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16(h)	2.00	Nos	971.00	1942.00	INR One Thousand Nine Hundred & Forty Two Only
75	Providing and fixing CP BRASS Angle Valve HEAVY QUALITY (L&K or equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16(i)	6.00	Nos	571.00	3426.00	INR Three Thousand Four Hundred & Twenty Six Only
76	Providing and fixing CP BRASS Piller cock HEAVY QUALITY (L&K or equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16(j)	2.00	Nos	628.00	1256.00	INR One Thousand Two Hundred & Fifty Six Only
77	Providing and fixing of 110 mm dia PVC pipe 6 Kg/ Sq.cm for with special such as Tee, bend, socket, elbow etc including supply of all labour, material, T & P etc complete required for proper completion of work. CSI No. 26.17	5.00	RM	257.00	1285.00	INR One Thousand Two Hundred & Eighty Five Only
78	S/F high Tensile steel colour coated anti rust ,high temp resistant sheet with Tensile Strength 550 MPA hot dip metallic (zinc Aluminum Alloy (Zn-55%)(Al-45%) Coating 70GSM with total thickness not less than 0.50mm (TCT) Durashine make with necessary over laps including S/F Galvanized J/V Hook according to purlin with ,nut,washer and bitumen washers etc.including cost of material ,labour T&P etc and special fastener (HT) , nuts & washer provide dia by the company etc required for proper completion of work as per direction of E/I confirming 1.5. 1397:1993. CSI No. 26.60 (As per Old Schedule)	21.00	Sqm	885.00	18585.00	INR Eighteen Thousand Five Hundred & Eighty Five Only
79	Providing and fixing first quality white glazed "Orissa" pattern W.C.Pan Hindustan, Cera make. size 580 mm.(Hindustan,Cera Make) with out "P" trap including supply of all materials,labour and T&P etc.complete. CSI No. 27.01	1.00	Nos	2354.00	2354.00	INR Two Thousand Three Hundred & Fifty Four Only
80	Same as item No. 79 above but of European type. CSI No. 27.02	1.00	Nos	3154.00	3154.00	INR Three Thousand One Hundred & Fifty
81	Providing and fixing flat back 465 mm.x 355 mm x 265 mm. size lipped front unal basin of white glazed earthen ware first quality (Hindustan, Neycer make) I.S.I. marked including supply of all materials,labour and T&P etc. required for proper completion of the work. CSI No. 27.05	1.00	Nos	2369.00	2369.00	INR Two Thousand Three Hundred & Sixty Nine Only
82	Providing and fixing 550X400 mm wash hand basin of white glazed earthen ware first quality I.S.I. marked (Hindustan,Neycer / Cera make) including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.08	1.00	Nos	3156.00	3156.00	INR Three Thousand One Hundred & Fifty Six Only
83	Providing and fixing 10 litres low level PVC flushing cistern, COMPLETE WITH ALL FITTINGS including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.12	2.00	Nos	1320.00	2640.00	INR Two Thousand Six Hundred & Forty Only
84	Providing and fixing 600 mm x 450 mm beveled edge mirror of Atul,Kiran make glass with Indian polish 6.50 mm thick complete with back of 600 mm x 450 mm x 6 mm hard board sheet fixed to wooden cleats with C.P. brass screws and washers including supply of all materials, labour and T&P etc.required for proper completion of the work. CSI No. 27.15	2.00	Nos	962.00	1924.00	INR One Thousand Nine Hundred & Twenty Four Only
85	Providing and fixing 750 mm x 20 mm size C.P. brass towel rail of approved quality including brackets including supply of all materials,labour and T&P etc. required for proper completion of the work and cutting and making good the wall plaster etc. required for work. CSI No. 27.16	2.00	Nos	609.00	1218.00	INR One Thousand Two Hundred & Eighteen Only
86	Providing and fixing soap dish chromium plated with brackets fixed to wooden cleats with brass screws including supply of all materials,labour and T&P etc.required for proper completion of the work. CSI No. 27.19	2.00	Nos	265.00	530.00	INR Five Hundred & Thirty Only
87	Supply and fixing 100 mm.PVC trap India make of heavy approved quality complete with CI grating. including supply of all materials,labour and T&P etc. required for proper completion of the work. CSI No. 27.21 (b)	5.00	Nos	561.00	2805.00	INR Two Thousand Eight Hundred & Five Only
88	Providing and laying 75 mm Dia SWR, PVC (Finolex or equivalent) pipe including cost of excavation, C.C etc including its jointing and connection, all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.29 (a)	10.00	RM	278.00	2780.00	INR Two Thousand Seven Hundred & Eighty Only
89	Same as item No. 88 above but of 90mm Dia. CSI No. 27.29 (b)	10.00	RM	333.00	3330.00	INR Three Thousand Three Hundred & Thirty
90	Same as item No. 88 above but of 110mm Dia. CSI No. 27.29 (c)	18.00	RM	388.00	6984.00	INR Six Thousand Nine Hundred & Eighty Four Only



J.E



S.D.O.-I


A.E


E.E

Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement : 4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test.*All above operations to be done in order and as directed and specified by the Engineer-in-Charge : With average thickness of 120 mm and minimum thickness at khurra as 65 mm. CSI No. 28.28		171.88	Sqm	932.00	160192.16	INR One Lakh Sixty Thousand One Hundred & Ninety Two and Paise Sixteen Only
92	Circuit wiring using 2 runs of 4.0 sq.mm+ 1 run of 2.5 sqmm PVC insulated copper wire drawn in 25mm dia 2 mm thick PVC conduits. Power circuits being reckoned from distribution board to first Power control switch Boards. (for power points 15 Amp) PSI No. 221 (c)	17.00	RM	122.00	2074.00	INR Two Thousand & Seventy Four Only
93	Supply and fixing 6A to 32A SP MCB C curve- 10 KA PSI No. 1002	5.00	Nos	132.00	660.00	INR Six Hundred & Sixty Only
94	d) 63 Amp. Isolator PSI No. 1005 (B)	1.00	Nos	595.00	595.00	INR Five Hundred & Ninety Five Only
95	Surface flush mounted 8 ways S.P.N. distribution board. PSI No. 1024	1.00	Nos	1470.00	1470.00	INR One Thousand Four Hundred &
96	P/F openable steel glazed windows and ventilators of standard rolled Z section conforming to IS 7452 1974 and welded with (100x20x5) mm holdfast embedded in C.C. block (23x11.5x7.5) cm size of 1:2:4 proportion of cement, coarse sand, & 20mm graded stone ballast as per drawing etc. complete but excluding S/F of glass panes of 4mm thick with nuts glazing clips with special putty of approved make etc. The fabrication should conform to IS 1038 1975. including cost of all materials, labour & T&P etc. (Rate already Sanction by Agr. No. 14/2018-19)	5.00	Sqm	1457.00	7285.00	INR Seven Thousand Two Hundred & Eighty Five Only
97	Same as Item no. 96 above but for fixed portion. (Rate already Sanction by Agr. No. 14/2018-19) NSI	3.00	Sqm	850.00	2550.00	INR Two Thousand Five Hundred & Fifty Only
Total in Figures					951912.16	INR Nine Lakh Fifty One Thousand Nine Hundred & Twelve and Paise Sixteen Only
Quoted Rate in Figures					0.00	INR Zero Only
Quoted Rate in Words					Select	INR Zero Only


J.E


SDO-I


A.E


E.E

S.E