

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के अन्तर्गत विद्युत नगरीय वितरण खण्ड-अष्टम, शिप्रा सनसिटी, इन्दिरापुरम, गाजियाबाद के कार्यक्षेत्र में उपभोक्ताओं का लाईन सम्बन्धी कार्य जमा योजना में बाह्य एजेन्सी के माध्यम से कराये जाने का कार्य।
Qty. of individual item variation $\pm 10\%$.

Contract No: 0120 2607114

Name of the Bidder/ Bidding							
<div>PRICE SCHEDULE FOR SHORT TERM E-TENDER NO-09/W/2022-23/D-VIII/EUDC-II/GZB</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable</div>							
NUMBER	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के अन्तर्गत विद्युत नगरीय वितरण खण्ड-अष्टम, शिप्रा सनसिटी, इन्दिरापुरम, गाजियाबाद के कार्यक्षेत्र में उपभोक्ताओं का लाईन सम्बन्धी कार्य जमा योजना में बाह्य एजेन्सी के माध्यम से कराये जाने का कार्य Qty. of individual item variation ± 10%.						
1.01	Carriage of 11 meter STP Pole from Store center Sahibabad/ Ghaziabad/Noida to different site of work including loading & unloading at both side.	22	No.	INR		0.00	INR Zero Only
1.02	Carriage of all line materials such as 15 No. top channel, 11 No. dropper channel, 66 No.11 KV Pin Insulator and other line material from store center Sahibabad/Ghaziabad/Noida to different site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
1.03	Carriage of 2122 meter 11 KV XLPE Cable 3x70 mm2 and other line material from store centerSahibabad/ Ghaziabad/Noida to different site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
1.04	Carriage of 15 meter Weasel Conductor, 11 No. LTTVM Meter, 90 Meter 3.5 sqmm LT cable from LTTVM, 150 Meter 1x70 sqmm LT Cable, 150 Meter Aluminium Cable XLPE, 11 No. Fuse Set 11 KV, 28 No. Earth Rod 2540X20mm, 28 No.Cable Box O/D 11 KV 3X70 XLP and other line material from store center Sahibabad/ Ghaziabad/Noida to different site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
1.05	Carriage of 07 No. 63 KVA & 04 No. 100 KVA T/F with MCCB from store center Sahibabad/ Ghaziabad/Noida to different site including loading & unloading at both end.	1	Job	INR		0.00	INR Zero Only
1.06	Erection of STP double Pole (11 DP) after digging of pits in proper size and fixing of all material on pole & refilling by earth, complete work in all respect as per RESPO norms.	22	No.	INR		0.00	INR Zero Only
1.07	Laying of 11 KV XLPE cable after digging of trenchless (size 11 KV XLPE cable 70x3 mm2). Complete work in all respect as per RESPO norms.	1900	Meter	INR		0.00	INR Zero Only
1.08	Fixing of cable jointing kit (size 11 KV XLPE cable 70x3 mm2 cable box) complete work in all respect as per RESPO norms.	40	No.	INR		0.00	INR Zero Only
1.09	Fixing of T/F of size 63/100 on DP Structure complete work in all respects.	11	No.	INR		0.00	INR Zero Only
2.00	Providing & fixing of Sundary items for Double Pole A) Holding Clamp/Cable Clamp.	84	Kg.	INR		0.00	INR Zero Only

2.01	Providing & fixing of Sundary items for Double Pole A) 11 KV TPMO SET	11	No.	INR		0.00	INR Zero Only
2.02	Providing & fixing of Sundary items for Double Pole A) Stone Pad as per RESPO norms.	22	No.	INR		0.00	INR Zero Only
2.03	Providing & fixing of Sundary items A) Cable Lug (120 Sq.mm.)	140	No.	INR		0.00	INR Zero Only
2.04	Providing Paint & Painting of Double Pole & other accessories A) Apply Red Oxide Paint & Aluminium Paint upto 7 feet from ground level as per IS.	22	No.	INR		0.00	INR Zero Only
2.05	Providing & fixing of Sundary items for Double Pole A) Number Plate (size 6x12 inch)	11	No.	INR		0.00	INR Zero Only
2.06	Providing & fixing of Sundary items for Double Pole A) Danger Board (FRP Sheet 12x18 inch)	11	No.	INR		0.00	INR Zero Only
2.07	Providing & fixing of Sundary items for Double Pole A) Barbado Wire (G.I. Wire 6/8 SWG)	22	Meter	INR		0.00	INR Zero Only
2.08	Providing & fixing of Sundary items for Double Pole A) Gi Pipe 6 inch dia	84	Meter	INR		0.00	INR Zero Only
2.09	Providing & fixing of Sundary items for 63 KVA T/F A) Gi Strip size 35x5 Sq. mm for 63 KVA T/F	210	Meter	INR		0.00	INR Zero Only
3.00	Providing & fixing of Sundary items for 100 KVA T/F A) Gi Strip size 40x6 Sq. mm for 100 KVA T/F	120	Meter	INR		0.00	INR Zero Only
3.01	Providing & fixing of Sundary items for 63/100 KVA T/F A) Chemical Earthing (11 No. body & 11 No. Neutral)	22	No.	INR		0.00	INR Zero Only
3.02	Providing & fixing of Sundary items for Double Pole A) Nut & Bolts	100	Kg.	INR		0.00	INR Zero Only
3.03	Grouting of Pole after digging of pits up to 2 meter depth and grouting material in ratio 1:4:8 with cement, sand and concrete as per norms of nigam. Complete work in all respect as per RESPO normes.	22	No.	INR		0.00	INR Zero Only
3.04	Grouting of stay set after digging of pits up to 1.5 to 2 meter depth and grouting material in ratio 1:4:8 with cement, sand and concrete as per norms of nigam. Complete work in all respect as per RESPO normes.	11	No.	INR		0.00	INR Zero Only
3.05	Laying of 11 KV XLPE cable of size 3x70 Sq.mm through trenchless system at road crossing through HDPE Method pipe of 6 inches dia. Complete work in all respect as per RESPO Norms.	68	Meter	INR		0.00	INR Zero Only
3.06	Installation of LT TVM Meter, Making Connections etc. (All consumable material required for proper completion of work should be provided by the contractor). Complete work in all respect as per RESPO Norms.	11	No.	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					