

Item Rate BoQ

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत सारणीय शिरण मण्डल-दिलीय, गाजियाबाद के अन्तर्गत विद्युत सारणीय शिरण खण्ड-यारह, गाजियाबाद के कार्यक्षेत्र में अतिरिक्त विजनेस प्लान मद में 02 नग 250 केबीएए परियोजना स्थापित करना, केबिल डालना व केबिकल अर्थिंग आदि का कार्य वायर एजेंसी के माध्यम से कराने हेतु।

Contract No: 0120 2607114

PRICE SCHEDULE FOR VERY SHORT TERM E-TENDER NO-15W/2023-24/D-XI/EUDC-II/GZB													
This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only (GST EXTRA as applicable)													
TEXT #													
Sl No.	Item Description	NUMBER	TEXT #	Quoted Currency in INR / Other Currency	TEXT #	BASIC RATE In Figures To be entered by the Bidder Rs. P	NUMBER #	TOTAL AMOUNT Without Taxes	TEXT #	TOTAL AMOUNT In Words	TEXT #		
1	विद्युत सारणीय शिरण मण्डल-दिलीय, गाजियाबाद के अन्तर्गत विद्युत सारणीय शिरण खण्ड-यारह, गाजियाबाद के कार्यक्षेत्र में अतिरिक्त विजनेस प्लान मद में 02 नग 250 केबीएए परियोजना स्थापित करना, केबिल डालना व केबिकल अर्थिंग आदि का कार्य वायर एजेंसी के माध्यम से कराने हेतु।	3	4	5	6	7	8						
1 00	Construction of plinth of size 2MX2MX1.5M above ground level and one ft. below the ground level of 9". After excavation of 4" earth, brick ballast shall be provided and rammering will be done properly after that a retaining wall of 9" width by first class brick in ratio 1:4 of cement and sand shall be made. The earth shall be filled upto one ft. below the top of the plinth. After this brick ballast shall be provided upto 6" from the earth level and proper rammering shall be done. One no. jaal of 12mm MS Tor shall be fixed in the hollow of the plinth and one ft. thick RCC in 1:2:4 ratio of cement, sand and stone ballast shall be laid on the top of the plinth. The 12mm thick plastering shall be done all around the plinth in ratio 1:4 ratio of cement and sand. The contractor shall be responsible to complete the work as per direction of supervising Engineer. It includes the cost of labour, T&P, carrier etc. required for proper completion of the work (This material will be provided by the Contractor)	2		INR		Job	0.00	INR Zero Only					
1 02	Fabrication of wire mesh fencing frames of different size fabricate out of MS angle iron of size 3x3x2M. Each frame duly welded and fixing with wire mesh of size 25x25x10 SWG hot dipped galvanized within the frame pressed under MS flats of size 40x5mm inside the angle on all four side with help of approx. 20No. Bolts & Nuts of 10mm diameter 45cm legs of frame will be grouted in 1:2:4 cement coarse sand and 20mm gauge stone blast in the size of 0.22x0.22x0.45meter. Each will be painted with one coat of red oxide and two coat of Alluminium paint of approved mark after proper cleaning. Fixing of wire mess fencing around on plinth of T/F with wire gauge 35x35x5mm with gate.	2	Job	INR			0.00	INR Zero Only					
1 03	Sale Carriage of LT ABC (3x120+1x70+1x16) SQ MM from Store Centre Sahibabad/ Ghaziabad/Noida to site of work including loading and unloading at both ends.	440	Mtr.	INR			0.00	INR Zero Only					
1 04	Sale Carriage of LT AL Cable (3x185 SQ MM) from Store Centre Sahibabad/ Ghaziabad/Noida to site of work including loading and unloading at both ends.	220	Mtr.	INR			0.00	INR Zero Only					
1 05	Sale Carriage of 250 KVA Transformer from Store Centre, Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side and installation with Complete work as per requirement of site including all the accessories.	2	No.	INR			0.00	INR Zero Only					
1 06	Carriage of ST Pole 11 Mtrs. Long from Store Centre Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side and installation with Complete work as per requirement of site including all the accessories.	4	No.	INR			0.00	INR Zero Only					
1 07	Carriage of PCC pole 8.5 Mtrs. Long from Store Centre Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side and installation with Complete work as per requirement of site including all the accessories.	15	No.	INR			0.00	INR Zero Only					
1 08	Earthing of Pole by M.S. Earthing Rod size 20x2500 mm & 6 SWG Earthing wire & GI wire/earth wire etc. (All the required material shall be provided by the contractor). Complete work as per requirement of site and as per RESPO norms.	19	No.	INR			0.00	INR Zero Only					
1 09	Laying of LT AB Cable (3x120+1x70+1x16 SQ MM) as per RESPO norms.	440	Mtr.	INR			0.00	INR Zero Only					
2 00	Laying of LT AL Cable (3x185 SQ MM) as per RESPO norms.	220	Mtr.	INR			0.00	INR Zero Only					
2 01	Work of Chemical Earthing of 250 KVA TF 02 Body & 02 Neutral with all material provided by the contractor. Complete work as per RESPO norms.	4	No.	INR			0.00	INR Zero Only					
2 02	Carriage of 11KV Cable Jointing kit of size 3x185 Sq mm Outdoor from Store Centre Sahibabad/ Ghaziabad/Noida to site of work & Fixing the same as per RESPO norms.	2	No.	INR			0.00	INR Zero Only					
2 03	Providing & Fixing Stone Pad as per RESPO Norms.	19	No.	INR			0.00	INR Zero Only					
2 04	Providing & Fixing Pole Clamps with Nut & Bolts as per RESPO Drawing.	44	No.	INR			0.00	INR Zero Only					
2 05	Providing & Fixing Suspension Clamp with I-Hook as per RESPO Drawing.	20	No.	INR			0.00	INR Zero Only					
2 06	Providing & Fixing Dead End Clamp with I-Hook as per RESPO Drawing.	4	No.	INR			0.00	INR Zero Only					
2 07	Providing & Fixing 3 Phase Distribution Box as per RESPO norms.	14	No.	INR			0.00	INR Zero Only					
2 08	Providing & Fixing PRC Clamp as per RESPO Drawing.	14	No.	INR			0.00	INR Zero Only					
2 09	Providing & Fixing M.S. Angle 50x50x6 mm as per RESPO Drawing.	125	Kg.	INR			0.00	INR Zero Only					
3 00	Providing & Fixing M.S. Channel 100x50 mm as per RESPO Drawing.	150	Kg.	INR			0.00	INR Zero Only					
3 01	Providing & Fixing GI Stay Wire 4mm 7/8 SWG as per RESPO Drawing.	220	Kg.	INR			0.00	INR Zero Only					
Total in Figures							INR Zero Only						
Quoted Rate in Words							INR Zero Only						