

Item Rate Boq

Validate

Print

Help

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण मण्डल-दिलीप, गाजियाबाद के अन्तर्गत बिजनेस प्लान वर्ष 2023-24 के मंद में 11/0.4 कोठी उपकेन्द्रों का निर्माण व क्षमतावृद्धि आदि कार्य सेमी टर्न-की के आधार पर ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने के सम्बन्ध में।

Contract No: 0120 2607114

Name of the Bidder/ Bidding Firm / Company	
--	--

PRICE SCHEDULE FOR E-TENDER NO-10/M/2023-24/EUDC-2/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable

NUMBER #	TEXT #	Item Description	NUMBE	TEXT #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.			Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2		3	4	5	6	7	8	
1.00		विद्युत नगरीय वितरण मण्डल-दिलीप, गाजियाबाद के अन्तर्गत बिजनेस प्लान वर्ष 2023-24 के मंद में 11/0.4 कोठी उपकेन्द्रों का निर्माण व क्षमतावृद्धि आदि कार्य सेमी टर्न-की के आधार पर ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने के सम्बन्ध में।						0.00	INR Zero Only
1.01		Construction of plinth of size 2MX2MX1.5M above ground level and one ft. below the ground level of 9". After excavation of 4" earth, brick ballast shall be provided and rammering will be done properly after that a retaining wall of 9" width by first class brick in ratio 1:4 of cement and sand shall be made. The earth shall be filled upto one ft. below the top of the plinth. After this brick ballast shall be provided upto 6" from the earth level and froper rammering shall be done. One no. jal of 12mm MS Tor shall be fixed in the hollow of the plinth and one ft. thick RCC in 1:2:4 ratio of cement, sand and stone ballast shall be laid on the top of the plinth. The 12mm thick plastering shall be done all around the plinth in ratio 1:4 ratio of cement and sand. The contractor shall be responsible to complete the work as per direction of supervising Engineer. It includes the cost of labour, T&P, carrier etc. required for proper completion of the work. (This material will be provided by the Contractor).	31	No.	INR				
1.02		Fabrication of wire mesh fencing frames of different size fabricate out of MS angle iron of size 3x3x2M. Each frame duly welded and fixing with wire mesh of size 25x25x10 SWG hot dipped galvanized within the frame pressed under MS flats of size 40x5mm inside the angle on all four side with help of approx. 20No. Bolts & Nuts of 10mm diameter 45cm legs of frame will be gouted in 1:2:4 cement coarse sand and 20mm gauge stone blast in the size of 0.22x0.22x0.45meter. Each will be painted with one coat of red oxide and two coat of Alluminium paint of approved mark after proper cleaning. Fixing of wire mess fencing around on plinth of T/F with wire gauge 25x25mm, MS Angle 35x35x5mm with gate.	33	No.	INR				0.00
1.03		Safe Carriage of 400 KVA Transformer from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and installation of TF at plinth including all accessories. Complete work as per requirement of site/RESPO norms.	17	No.	INR				0.00
1.04		Safe Carriage of 250 KVA Transformer from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and installation of TF at plinth including all accessories. Complete work as per requirement of site/RESPO norms.	34	No.	INR				0.00
1.05		Safe Carriage of ST Pole 11 Meter long from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Erection/Installation of poles including all accessories. Complete work as per requirement of site.	48	No.	INR				0.00
1.06		Safe Carriage of 34 No. PCC Pole 8.5 Meter long and 33 No. PCC Pole 09 Meter long from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Erection/Installation of poles including all accessories. Complete work as per requirement of site.	67	No.	INR				0.00
1.07		Safe Carriage of ABC Cable 3x120-1x95+1x16 Sq.mm Cable from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, stringing, binding, sagging & jumpering etc. Complete the work as per requirement of site/RESPO norms.	9755	Mtr.	INR				0.00
1.08		Safe Carriage of 390 Meter LT XLPE 1x240 Sq.mm Cable, 705 Meter 1x400 Sq.mm Cable & 220 Meter 1x630 Sq.mm Cable from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, stringing, binding, sagging & jumpering etc. Complete work as per requirement of site/RESPO norms.	1315	Mtr.	INR				0.00

1.08	Safe Carriage of 200 Meter XLPE 1x35 Sq.mm and 1225 Meter 3x70 Sq.mm Cable from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, stringing, binding, sagging & jumpering etc. Complete work as per requirement of site/RESPO norms.	1425	No.	INR			0.00	INR Zero Only
2.00	Safe Carriage of XLPE Cable Box/Jointing Kit 3x70 Sq.mm (Outdoor) from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and fixing the same at site.	10	No.	INR			0.00	INR Zero Only
2.01	Safe Carriage of 1T XLPE Cable 3.5x240 Sq.mm from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, stringing, binding, sagging & jumpering etc. Complete work as per requirement of site/RESPO norms.	30	Mtr.	INR			0.00	INR Zero Only
2.02	Safe Carriage of 285 No. 11 KV Composite Polymeric Pin Insulator and 147 No. 11 KV Disc Insulator 45 kN from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end.	432	No.	INR			0.00	INR Zero Only
2.03	Safe Carriage of 67 No. 11 KV Disc Insulator Fittings 45 kN from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end.	67	No.	INR			0.00	INR Zero Only
2.04	Safe Carriage of 1610 Meter ACSR Dog Conductor and 726 Meter ACSR Weasel Conductor from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, Sagging, Stringing, Binding & Jumpering etc. Complete the work as per RESPO norms and requirement of site.	2336	Mtr.	INR			0.00	INR Zero Only
2.05	Safe Carriage of ACSR Weasel Winding from store Center Ghaziabad /Sahibabad /Noida to site of work including loading and unloading at both end and Laying, Sagging, Stringing, Binding & Jumpering etc. Complete the work as per RESPO norms and requirement of site.	155	Mtr.	INR			0.00	INR Zero Only
2.06	Work of dismantling of old/damaged ABC/XLPE Conductor from site of work to Store Centre/JE Store including loading and unloading at both end.	500	Mtr.	INR			0.00	INR Zero Only
2.07	Work of Chemical Earthing by providing all the required material for completion of work. Complete the work as per RESPO norms.	76	No.	INR			0.00	INR Zero Only
2.08	Work of Concreting/Grouting of pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	115	No.	INR			0.00	INR Zero Only
2.09	Work of Earthing of pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	93	No.	INR			0.00	INR Zero Only
3.00	Providing and fixing of Sundary Items A) MS Clamp for STP	172	No.	INR			0.00	INR Zero Only
3.01	Providing and fixing of Sundary Items A) SMS Clamp for PCC Pole	41	No.	INR			0.00	INR Zero Only
3.02	Providing and fixing of Sundary Items A) Copper L-Piece	20	No.	INR			0.00	INR Zero Only
3.03	Providing and fixing of Sundary Items A) M.S Channel 100x50x5mm	2394	Kg.	INR			0.00	INR Zero Only
3.04	Providing and fixing of Sundary Items A) M.S Channel for Fuse Set	3	No.	INR			0.00	INR Zero Only
3.05	Providing and fixing of Sundary Items A) G.I. Wire 5mm 6 SWG.	213	Kg.	INR			0.00	INR Zero Only
3.06	Providing and fixing of Sundary Items A) G.I. Strip 25x3 mm	64	Kg.	INR			0.00	INR Zero Only
3.07	Providing and fixing of Sundary Items A) 11 KV TPMO	7	No.	INR			0.00	INR Zero Only
3.08	Providing and fixing of Sundary Items A) 11 KV Fuse Set	10	No.	INR			0.00	INR Zero Only
3.09	Providing and fixing of Sundary Items A) 11 KV V Type Steel Cross Arm	16	No.	INR			0.00	INR Zero Only
4.00	Providing and fixing of Sundary Items A) Cross Arm Holding Clamps with Nut & Bolts.	20	No.	INR			0.00	INR Zero Only
4.01	Providing and fixing of Sundary Items A) Aluminium Bus Bar	28	No.	INR			0.00	INR Zero Only
4.02	Providing and fixing of Sundary Items A) Piercing Clamps.	291	No.	INR			0.00	INR Zero Only
4.03	Providing and fixing of Sundary Items A) Piercing Connector.	97	No.	INR			0.00	INR Zero Only
4.04	Providing and fixing of Sundary Items A) Suspension Clamp with I-Hook.	275	No.	INR			0.00	INR Zero Only
4.05	Providing and fixing of Sundary Items A) Dead End Clamp with I-Hook.	50	No.	INR			0.00	INR Zero Only
4.06	Providing and fixing of Sundary Items A) PG Clamp 120 Sq.mm	32	No.	INR			0.00	INR Zero Only

4.07	Providing and fixing of Sundry Items A) Pole Clamp with Nut & Bolts	220	No.	INR	0.00	INR Zero Only
4.08	Providing and fixing of Sundry Items A) LT Insulator with Clamp.	120	No.	INR	0.00	INR Zero Only
4.09	Providing and fixing of Sundry Items A) Nutt & Bolts with Washer.	225	Kg.	INR	0.00	INR Zero Only
5.00	Providing and fixing of Sundry Items A) All Crimping Lug 1x70 Sq. mm.	96	No.	INR	0.00	INR Zero Only
5.01	Providing and fixing of Sundry Items A) All Crimping Lug 1x120 Sq. mm.	16	No.	INR	0.00	INR Zero Only
5.02	Providing and fixing of Sundry Items A) All Crimping Lug 1x240 Sq. mm.	40	No.	INR	0.00	INR Zero Only
5.03	Providing and fixing of Sundry Items A) All Crimping Lug 1x400 Sq. mm.	28	No.	INR	0.00	INR Zero Only
5.04	Providing and fixing of Sundry Items A) All Crimping Lug 1x630 Sq. mm.	44	No.	INR	0.00	INR Zero Only
5.05	Providing and fixing of Sundry Items A) Stone Pad.	83	No.	INR	0.00	INR Zero Only
5.06	Providing and fixing of Sundry Items A) Danger Board.	3	No.	INR	0.00	INR Zero Only
5.07	Providing and fixing of Sundry Items A) Top Channel.	5	No.	INR	0.00	INR Zero Only
5.08	Providing and fixing of Sundry Items A) G.I. Dropper Channel.	8	No.	INR	0.00	INR Zero Only
5.09	Providing and fixing of Sundry Items A) 3 Phase Distribution Box.	88	No.	INR	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				