

Tender Inviting Authority: Superintending Engineer Electricity Civil Distribution Circle, PVVNL, Meerut.

Name of Work: Maintenance & other Miscellaneous civil Repair work of Building of Test lab IV under Test Div-2 Distt- Saharanpur


T.S. No: 69/E.C.D.C.,/ MRT/2022-23

Name of the
Bidder/
Bidding Firm
Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	4	5	6	7	8
1	Excavation in foundation in ordinary soil (loam, clay or sand) including lift upto 1.5 Metre and lead upto 30 metre including filling, watering, and ramming of excavated earth into the trenches or into the space between the building and the side of the foundation or in to the plinth and removal & disposal of surplus earth as directed by the E/I up to a distance of 30m from the foundation trenches. CSI No. 4.01	2.00	Cum	195.00	390.00	INR Three Hundred & Ninety Only
2	Earth filling under floors and/or substation area including cost of the earth when obtained from within 8 km Outside UPPCL area including its royalty and Carriage including watering, ramming in 20cm thick layers and dressing of earth etc. All complete. CSI No. 4.10	6.00	Cum	433.00	2598.00	INR Two Thousand Five Hundred & Ninety Eight Only
3	Concrete with 4cm gauge stone ballast, coarse sand (F.M. 1.8 to 2.5) & cement in proportion of 12 6 1 in foundations & under floors including supply of all materials, labour and tools and plants etc. required for proper completion. CSI No. 5.02	0.50	Cum	5509.00	2754.50	INR Two Thousand Seven Hundred & Fifty Four and Paise Fifty Only
4	Cement concrete with 2cm gauge approved hard stone ballast, coarse sand (F.M. 1.8 to 2.5) and cement in proportion of 4:2:1 including supply of all materials, labour, side shuttering if required and T&P etc. required for proper completion of work. CSI No. 5.06	1.00	Cum	7085.00	7085.00	INR Seven Thousand & Eighty Five Only
5	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:2.4 in lintels of doors and windows, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.10	0.50	Cum	8252.00	4126.00	INR Four Thousand One Hundred & Twenty Six Only
6	Precast cement concrete door sills, chaukhats boundary posts, shelves and similar small work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast in the proportion 1:1.5:3, excluding reinforcement but including fixing the same in position including cost of all other material, labor and T&P. CSI No. 5.22	0.10	Cum	9088.00	908.80	INR Nine Hundred & Eight and Paise Eighty Only
7	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:1.5:3 in lintels of doors and windows, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.23	0.15	Cum	8742.00	1311.30	INR One Thousand Three Hundred & Eleven and Paise Thirty Only
8	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in Slab, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.24	0.10	Cum	10060.00	1006.00	INR One Thousand & Six Only
9	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in raft foundation and footings excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.27	0.20	Cum	8344.00	1668.80	INR One Thousand Six Hundred & Sixty Eight and Paise Eighty Only
10	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in RCC T-Beam slab and column excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.29	0.20	Cum	11048.00	2209.60	INR Two Thousand Two Hundred & Nine and Paise Sixty Only
11	1st class brick (not less than class 150) work in 1:6 C.M. with cement and coarse sand (2.9 to 3.2 F.M) mortar in foundation and plinth including supply of all material, labour and T&P etc. required for proper completion of work. CSI No. 6.01	1.50	Cum	4864.00	7296.00	INR Seven Thousand Two Hundred & Ninety Six Only
12	Same as item no. 11 above but for wall of one brick thickness Add extra for Labour to the rate of item no 6.01 CSI No. 6.01+6.08	1.50	Cum	5183.00	7774.50	INR Seven Thousand Seven Hundred & Seventy Four and Paise Fifty Only
13	Same as item no. 11 above but for wall of half brick 4.5" (115 mm) thick but in 1:6 C.M. with cement and coarse sand of 2.25 F.M. mortar. CSI No. 6.01+6.09	0.20	Cum	5343.00	1068.60	INR One Thousand & Sixty Eight and Paise Sixty Only
14	Brick work in foundation & plinth with old dismantled bricks (supplied by department free of cost) and coarse sand of F.M. 1.8 to 2.5 mortar in 1:6 including supply of all other materials, labour, removing mortar & cleaning of old & used bricks, T&P etc complete. CSI No. 6.18	1.00	Cum	2814.00	2814.00	INR Two Thousand Eight Hundred & Fourteen Only


 JE


 SDO


 E.E

15	Removal of cement mortar from dismantled bricks and stacking in countable position at place as directed by Engineer in charge including cost of all materials labour and T&P required for proper completion of work . CSI No. 6.22	1.00	%o	1357.00	1357.00	INR One Thousand Three Hundred & Fifty Seven Only
16	25mm.thick Damp proof course with cement concrete consisting of 1 part cement, 1½ parts approved coarse sand and 3 parts approved 12 mm graded stone grit and also including liquid water proofing material as approved Engineer-in-charge in proportion as specified by the manufacturer. CSI No. 7.02	2.00	Sqm	339.00	678.00	INR Six Hundred & Seventy Eight Only
17	Supply and fixing of 32 mm thick single leaf flush door shutter (boiled water resistance, phenol maldehyde resin bonded, hot pressed factory made) commercial quality to I.S.2202 part-1 (1983) ISI marked including fixing of wooden cleats and stoppers and including fixing and adjustment of hinges, bolts, locks, handles, springs and other fittings but excluding their supply including all materials, labour & T&P etc. required for proper completion of work. CSI No. 8.57	2.00	Sqm	1927.00	3854.00	INR Three Thousand Eight Hundred & Fifty Four Only
18	Supplying and fixing 24 Gauge Anodized aluminium sheet of approve quality including cutting, wastage and fixing the same over the wooden door shutters with nails with all materials, labour and T&P CSI No. 8.63	5.00	Sqm	411.00	2055.00	INR Two Thousand & Fifty Five Only
19	Mild Steel or Iron work in heavy sizes such as trusses built up gates, door frames, record, racks roof work gates etc. wrought to required form including holes rivetting or welding where necessary and also fixing in proper position and alignment including cost of all materials supplied by contractor. CSI No. 9.01	0.100	M.T.	98843.00	9884.30	INR Nine Thousand Eight Hundred & Eighty Four and Paise Thirty Only
20	TMT/Iron steel in plain work such as reinforced concrete or reinforced brick work (when not included in an over all rates) wrought to required shape as necessary including bending for proper completion of the work and including supply of steel its wastage, bend, hooks and authorized overlapping shall be measured. (Steel shall be arranged by the contractor). CSI No. 9.03	0.050	M.T.	87899.00	4394.95	INR Four Thousand Three Hundred & Ninety Four and Paise Ninety Five Only
21	Providing and fixing steel glazed window and ventilator of standard rolled Mann or mahavir steel sections conforming to IS 7452-1947 as per drawing joints metered & welded with 100*14*3.15 mm holdfast embedded in cement concrete block 15*10*10 cm size of 1:3:6 proportion i.e. 1 part cement 3 part approved coarse sand & 6 part of graded stone (aggregated 20 mm nominal size) S/F of glass pan of plain pin headed 4 mm. Thick nuts glazing clips and special putty of approved make completed and including a cost of red oxide pain. The Fabrication should conform to I.S. 1038-1975 (aluminum beading with rubber packing include) CSI No. 9.17	2.00	Sqm	4255.00	8510.00	INR Eight Thousand Five Hundred & Ten Only
22	Supply and fixing galvanised mosquito proof jali (16x24 gauge) with M.S. flat of 20 x 3 mm. size, on both sides screwed or welded to window or door frame. CSI No. 9.18	2.00	Sqm	728.00	1456.00	INR One Thousand Four Hundred & Fifty Six Only
23	Supply and Fixing 24 B.W.G , G.C. Iron sheet roofing fixed in position with J or U bolts 10 mm dia with G.I. Limpet & bitumen washers including supply of all material, labour, wastage and T&P etc required for proper completion of work. CSI No. 10.01	6.00	sqm	679.00	4074.00	INR Four Thousand & Seventy Four Only
24	Supply and Fixing 24 B.W.G Galvanized Iron Ridges valley and gutters for roofing fixed with J or U bolts 10 mm dia with G.I. Limpet & bitumen washers including supply of all material, labour, wastage and T&P etc required for proper completion of work. CSI No. 10.02	3.00	RM	497.00	1491.00	INR One Thousand Four Hundred & Ninety One Only
25	Supply and painting of 80/100 grade bitumen paint over roof or on wall @1.7 kg/sq.m. Including sweeping, cleaning the roof with brush, heating the paint to required temperature and supply of all materials, labour and T&P etc. required for proper completion of work. CSI No. 10.05	80.00	Sqm	71.00	5680.00	INR Five Thousand Six Hundred & Eighty Only
26	Supply and laying one layer of tar felt or any other equivalent approved materials at the junction of wall & roof or at any place as per direction of the Engineer – in charge including necessary overlap, applying a coat of approved mastic paints below the Tar felt & including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 10.06	72.00	Sqm	416.00	29952.00	INR Twenty Nine Thousand Nine Hundred & Fifty Two Only
27	As in Item No. 26 but applying one coat of approved mastic paint on the bottom and one coat at top of Tar felt. CSI No. 10.07	72.00	Sqm	570.00	41040.00	INR Forty One Thousand & Forty Only
28	12 mm thick plaster with cement mortar consisting of one part of cement & four part of coarse sand (1:4), minimum thickness not to be less than 10 mm including supply of all material, labour and T&P etc for proper completion of work. CSI No. 11.07	30.00	Sqm	192.00	5760.00	INR Five Thousand Seven Hundred & Sixty Only
29	Same as item No. 28 above but with 1:6 cement and coarse sand mortar. CSI No. 11.09	60.00	Sqm	182.00	10920.00	INR Ten Thousand Nine Hundred & Twenty Only
30	Add for extra labour to all items of plaster if done in ceiling. CSI No. 11.10	75.00	Sqm	21.40	1605.00	INR One Thousand Six Hundred & Five Only
31	Add for extra labour and Materials for plaster over rough face of one brick thick wall. CSI No. 11.12	15.00	Sqm	25.00	375.00	INR Three Hundred & Seventy Five Only
32	2 cm (3/4") thick cement plaster in dado or skirting in 1:2 C.M. consisting of one part of cement and two parts of approved coarse sand laid in panels finished with 3mm (1/8") thick floating coat of neat cement or cement and marble dust in ratio of 5:1 including supply of all materials, labour and T&P etc. required for proper completion of the work CSI No. 11.13	5.00	Sqm	282.00	1410.00	INR One Thousand Four Hundred & Ten Only
33	Providing (12x15) mm section groove in plaster including all material, labour and T&P etc. required for proper completion of the work. CSI No. 11.16	10.00	RM	12.00	120.00	INR One Hundred & Twenty Only
34	Making drip course (25x12) mm in 1:2 cement and coarse sand including supply of all materials, labour and T&P etc required for proper completion of work. CSI No. 11.19	25.00	RM	12.00	300.00	INR Three Hundred Only
35	3 mm thick floating coat of neat cement finish including supply of all materials, labour and T&P etc. required for proper completion of the work. (cement consumption 0.044 bag/Sq.m.) CSI No. 11.20	18.00	Sqm	21.00	378.00	INR Three Hundred & Seventy Eight Only

CS

Shub

Shub

36	40 cm thick 1:2:4 plain cement concrete floor with cement, approved coarse sand & 2cm graded approved stone ballast laid in panels finished with 3mm floating coat of neat cement or cement and marble dust in ratio of 5:1 as specified and including 7.5 Cm thick base concrete consisting of cement coarse sand and 4 cm 1 class brick ballast in the proportion of 1:6:12 and removing any overlapping mortar at the joints of the panels if any and giving them a uniform finish including supply of all materials, labour and T&P etc, required for proper completion of the work. CSI No. 12.03	18.00	Sqm	752.00	13536.00	INR Thirteen Thousand Five Hundred & Thirty Six Only
37	40 cm thick 1:2:4 plain cement concrete floor with cement, approved coarse sand & 2cm graded approved stone ballast laid in panels finished with 3mm floating coat of neat cement or cement and marble dust in ratio of 5:1 as specified and removing any overlapping mortar at the joints of the panels if any and giving them a uniform finish including supply of all materials, labour and T&P etc, required for proper completion of the work. without base CC. CSI No. 12.04	18.00	Sqm	413.00	7434.00	INR Seven Thousand Four Hundred & Thirty Four Only
38	First class bricks on Edge floor laid dry, joints sand filled, including preparation base to proper slope and its ramming including supply of all materials, labour and T&P etc, required for proper completion of the work. CSI No. 12.07	10.00	Sqm	546.00	5460.00	INR Five Thousand Four Hundred & Sixty Only
39	Providing and fixing glass strips of 3.15 mm thickness & 40mm depth in joints of floor and skirting at the time of laying floors, flush with floor level including supply of all materials, labour & T&P etc. required for proper completion of work. CSI No. 12.14	20.00	RM	33.00	660.00	INR Six Hundred & Sixty Only
40	Painting or varnishing new iron work in small areas or new wood work with one coat of ready mixed priming paint and one coat of approved superior quality ready mix paint "Luxol" or equivalent brand or varnish including supply of all materials, labour and T&P etc. required for proper completion of the work. Paint to be used should conform to the I.S. 103-1950. CSI No. 13.01	5.00	Sqm	77.00	385.00	INR Three Hundred & Eighty Five Only
41	Same as item No.40 above but for every coat after 1st coat. CSI No. 13.02	20.00	Sqm	36.00	720.00	INR Seven Hundred & Twenty Only
42	Same as item no. 40 above but every coat on previously painted old wood or steel work. CSI No. 13.03	25.00	Sqm	49.00	1225.00	INR One Thousand Two Hundred & Twenty Five
43	Removing Paint or varnish with paint remover or with caustic soda including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 13.07	20.00	Sqm	85.00	1700.00	INR One Thousand Seven Hundred Only
44	One priming coat and one coat oil bound distemper on new work including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 13.08	75.00	Sqm	69.00	5175.00	INR Five Thousand One Hundred & Seventy Five Only
45	Same as item No. 44 above but for every coat after the first coat. CSI No. 13.09	75.00	Sqm	28.00	2100.00	INR Two Thousand One Hundred Only
46	Same as item No. 44 above but for every coat on previously old distempered surface. CSI No. 13.10	200.00	Sqm	35.00	7000.00	INR Seven Thousand Only
47	Applying Birla or equivalent putty on new interior or exterior surface over one coat of water based cement primer of ICI or equivalent brand for smoothening and levelling of the surface as per requirement and direction of Engineer I/C including cost of all material, labour, T & P etc required for proper completion of work. CSI No. 13.20	30.00	Sqm	89.00	2670.00	INR Two Thousand Six Hundred & Seventy Only
48	Applying BIRLA PUTTY or equivalent putty on previously bila putty smoothen surface over one coat of water base cement primer of ICI or equivalent brand for smoothening and leveling of the surface as per requirement and direction of E/I including cost of all material, labour and T&P required for proper completion of work. CSI No. 13.21	100.00	Sqm	43.00	4300.00	INR Four Thousand Three Hundred Only
49	Painting one coat with APEX or equivalent brand weather coat paint on new wall surfaces (well prepared with Birla putty and one coat of primer ICI or equivalent which shall be paid separately) including through washing with water including cost of all materials, labour, T&P required for proper completion of work. CSI No. 13.22	20.00	Sqm	98.00	1960.00	INR One Thousand Nine Hundred & Sixty Only
50	Same as in item no 49 above but for every coat of additional APEX or equivalent brand weather coat paint. CSI No. 13.23	30.00	Sqm	43.00	1290.00	INR One Thousand Two Hundred & Ninety Only
51	Same as in item no 49 above but for every coat of additional APEX or equivalent brand weather coat paint coat paint previously treated surface. CSI No. 13.24	30.00	Sqm	65.00	1950.00	INR One Thousand Nine Hundred & Fifty Only
52	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by the Engineer-in-charge within a distance of 60 metres. CSI No. 15.01	2.00	Cum	575.00	1150.00	INR One Thousand One Hundred & Fifty Only
53	Dismantling reinforced cement concrete or reinforced brick work, including stacking of dismantled materials as directed by the Engineer-In-charge within a distance of 60 metres. CSI No. 15.03	1.00	Cum	1277.00	1277.00	INR One Thousand Two Hundred & Seventy Seven Only
54	Dismantling cement concrete or brick or granolithic floors including base concrete and including stacking of dismantled materials as directed by the Engineer In-charge within a distance of 60 metres. CSI No. 15.05	8.00	Sqm	66.00	528.00	INR Five Hundred & Twenty Eight Only
55	Dismantling doors and windows chowkhats including stacking of materials as directed by Engg-in-Charge within a distance of 60 meters. CSI No. 15.10	2.00	Sqm	74.00	148.00	INR One Hundred & Forty Eight Only
56	Dismantling existing plaster including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.11	150.00	Sqm	47.00	7050.00	INR Seven Thousand & Fifty Only
57	Scrapping old white or colour wash or distemper including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.12	250.00	Sqm	14.00	3500.00	INR Three Thousand Five Hundred Only
58	Dismantling of existing damaged Mud Faska over the roof Cleaning the surface with wire brush, removal and disposal of rubbish at a distance 100 meters also including the cost of cleaning and stacking of usable materials etc. including cost of all materials, labour, T&P required for proper completion of work. CSI No. 15.14	30.00	Sqm	158.00	4740.00	INR Four Thousand Seven Hundred & Forty Only

[Signature]

[Signature]

[Signature]

59	Renewing panes of 4.8 to 5.7 mm glass including supply of glass with putty and brads including supply of all materials, labour and T&P etc. required for proper completion of the work (a) glass of 4 mm thick. CSI No. 20.04 (b)	8.00	Sqm	838.00	6704.00	INR Six Thousand Seven Hundred & Four Only
60	Cleaning of Septic tank including disposal of wastage out side the UPPCL area as per directed by the Engineer-I/C including cost of all materials, labour, T&P required for proper completion of work CSI No. 20.12	1.00	Nos	1848.00	1848.00	INR One Thousand Eight Hundred & Forty Eight Only
61	Disposal of Rubbish / debris out side the UPPCL area directed by the Engineer-I/C including cartage labour, and materials, T&P required for proper completion of work. (no deduction for voids shall be made) CSI No. 20.16	2.00	cum	370.00	740.00	INR Seven Hundred & Forty Only
62	Supply and replacing of following chromium polished iron fittings including cost of nuts, bolts etc. complete. (a) L drops 16 mm dia x 300 long CSI No. 20.17 (a)	2.00	Nos	187.00	374.00	INR Three Hundred & Seventy Four Only
63	Same as item No 62 above but for (c) Tower bolts 10 mm dia x 100 mm long. CSI No. 20.17 (c)	2.00	Nos	64.00	128.00	INR One Hundred & Twenty Eight Only
64	Same as item No. 62 above but for (d) Iron hinges 100 mm size. 12 gauge. thick. CSI No. 20.17 (d)	3.00	Nos	77.00	231.00	INR Two Hundred & Thirty One Only
65	Same as item No. 62 above but for (f) M.S. handles 100 mm size. CSI No. 20.17 (f)	2.00	Nos	39.00	78.00	INR Seventy Eight Only
66	Laying chicken mesh of (20 mm) hexagonal heavy quality over roofs of joints of roof as per direction Engineer-in-charge. CSI No. 20.21	15.00	Sqm	82.00	1230.00	INR One Thousand Two Hundred & Thirty Only
67	Supply and replacing of angle holder of "Anchor" or equivalent make of approved quality including all materials, labour and T&P etc. CSI No. 22.01	2.00	Nos	43.00	86.00	INR Eighty Six Only
68	Supply and replacing of 6 Amp piano type Switch of "Anchor" or equivalent make of approved quality including all materials, labour and T&P etc. CSI No. 22.02	3.00	Nos	49.00	147.00	INR One Hundred & Forty Seven Only
69	Supply and replacing of 6 Amp piano type Socket of "Anchor" or equivalent make of approved quality including all materials, labour and T&P etc. CSI No. 22.03	5.00	Nos	60.00	300.00	INR Three Hundred Only
70	Supply and replacing of 16 Amp piano type Switch of "Anchor" or equivalent make of approved quality including all materials, labour and T&P etc. CSI No. 22.04	3.00	Nos	131.00	393.00	INR Three Hundred & Ninety Three Only
71	Supply and replacing of 16 Amp piano type Socket of "Anchor" or equivalent make of approved quality including all materials, labour and T&P etc. CSI No. 22.05	3.00	Nos	131.00	393.00	INR Three Hundred & Ninety Three Only
72	Supply and laying 1.5 Sqmm Gauge copper wire of plaza or equivalent make of approved quality including connecting with existing existing wiring in existing P.V.C. pipe including all materials labour and T&P completed CSI No. 22.06(a)	3.00	Nos	74.00	222.00	INR Two Hundred & Twenty Two Only
73	Supply and laying 2.5 Sqmm Gauge copper wire of plaza or equivalent make of approved quality including connecting with existing existing wiring in existing P.V.C. pipe including all materials labour and T&P completed CSI No. 22.06(b)	3.00	Nos	96.00	288.00	INR Two Hundred & Eighty Eight Only
74	Supply and laying 4 Sqmm Gauge copper wire of plaza or equivalent make of approved quality including connecting with existing existing wiring in existing P.V.C. pipe including all materials labour and T&P completed CSI No. 22.06(c)	3.00	Nos	123.00	369.00	INR Three Hundred & Sixty Nine Only
75	Providing and fixing 15 mm dia B-class Jindal, JTC, ISI marked G.I. pipes complete with special such as bend, tee, socket, cross, clamp etc earth work including filling the trenches etc required for proper completion of the work. the rate also includes concealed GI fitting where required, cutting and making good the walls etc and all materials, labour and T&P complete. CSI No. 26.01 (a)	3.00	RM	219.00	657.00	INR Six Hundred & Fifty Seven Only
76	Same as item No. 75 but for 20 mm dia. CSI No. 26.01 (b)	5.00	RM	268.00	1340.00	INR One Thousand Three Hundred & Forty
77	Same as item No. 75 but for 32 mm dia. CSI No. 26.01 (d)	2.00	RM	433.00	866.00	INR Eight Hundred & Sixty Six Only
78	Providing and fixing 15 mm dia Jindal, JTC, ISI marked G.I. pipes complete with special such as bend, tee, socket, cross, clamp etc earth work including filling the trenches etc required for proper completion of the work. the rate also includes external GI fitting where required, cutting and making good the walls etc and all materials, labour and T&P complete. CSI No. 26.02 (a)	5.00	RM	188.00	940.00	INR Nine Hundred & Forty Only
79	Same as Item No. 78 but for 20 mm dia. CSI No. 26.02 (b)	5.00	RM	230.00	1150.00	INR One Thousand One Hundred & Fifty Only
80	Same as Item No. 78 but for 32 mm dia. CSI No. 26.02 (d)	2.00	RM	371.00	742.00	INR Seven Hundred & Forty Two Only
81	Supply and fixing of Syntex or equivalent make water storage tank including all materials, labours, T&P etc required for proper completion of work. CSI No. 26.12	500.00	Ltr	11.00	5500.00	INR Five Thousand Five Hundred Only
82	Supply and fixing 15 mm dia CI/PVC bib cock including replacing of old bib cock complete. CSI No. 26.13 (c)	1.00	Nos	61.00	61.00	INR Sixty One Only
83	Providing and fixing CP BRASS BIB COCK 15 mm dia. HEAVY QUALITY (400gm) (L & K and equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16 (a)	2.00	Nos	678.00	1356.00	INR One Thousand Three Hundred & Fifty Six Only
84	Providing and fixing CP BRASS STOP COCK 15 mm dia. HEAVY QUALITY (400gm) (L & K and equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16 (c)	2.00	Nos	672.00	1344.00	INR One Thousand Three Hundred & Forty Four Only

Handwritten signature/initials.

Handwritten signature/initials.

Handwritten signature/initials.

85	Same as item No. 84 CP BRASS Angle Valve HEAVY QUALITY (L&K or equi.). CSI No. 26.16 (i)	2.00	Nos	571.00	1142.00	INR One Thousand One Hundred & Forty Two
86	Same as item No. 84 CONCEALED STOP COCK HEAVY QUALITY (L&K or equi). CSI No. 26.16 (k)	2.00	Nos	800.00	1600.00	INR One Thousand Six Hundred Only
87	Providing and fixing of 110 mm dia PVC pipe 6 Kg/ Sq.cm for with special such as Tee, bend, socket, elbow etc including supply of all labour,material,T & P etc complete required for proper completion of work. CSI No. 26.17	6.00	RM	261.00	1566.00	INR One Thousand Five Hundred & Sixty Six Only
88	Providing and fixing first quality white glazed "Orissa" pattern W.C.Pan Hindustan, Cera make. size 580 mm.(Hindustan,Cera Make) with out "P" trap including supply of all materials,labour and T&P etc.complete. CSI No. 27.01	1.00	Nos	2379.00	2379.00	INR Two Thousand Three Hundred & Seventy Nine Only
89	Providing and fixing 510X400 mm wash hand basin of white glazed earthen ware first quality I.S.I. marked (Hindustan,Neycer / Cera make) including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.09	1.00	Nos	3166.00	3166.00	INR Three Thousand One Hundred & Sixty Six Only
90	Providing and Fixing 10 Liters low level PVC flushing cistern, COMPLETE WITH ALL FITTINGS including supply of all materials, labour and T&P etc.required for proper completion of the work. CSI No. 27.12	1.00	Nos	1320.00	1320.00	INR One Thousand Three Hundred & Twenty Only
91	Providing and fixing 600 mm x 450 mm beveled edge mirror of Atul,Kiran makeglass with Indian polish 6.50 mm thick complete with back of 600 mm x 450 mm x 6 mm hard board sheet fixed to wooden cleats with C.P. brass screws and washers including supply of all materials, labour and T&P etc.required for proper completion of the work. CSI No. 27.15	1.00	Nos	968.00	968.00	INR Nine Hundred & Sixty Eight Only
92	Providing and fixing 750 mm x 20 mm size C.P. brass towel rail of approved quality including brackets including supply of all materials,labour and T&P etc. required for proper completion of the work and cutting and making good the wall plaster etc. required for work. CSI No. 27.16	1.00	Nos	616.00	616.00	INR Six Hundred & Sixteen Only
93	Providing and fixing soap dish chromium plated with brackets fixed to wooden cleats with brass screws including supply of all materials,labour and T&P etc.required for proper completion of the work. CSI No. 27.19	1.00	Nos	271.00	271.00	INR Two Hundred & Seventy One Only
94	Supply and fixing CP Nahani Trap India make of heavy approved quality complete with CI grating including supply of all materials,labour and T&P etc. required for proper completion of the work. CSI No. 27.21 (a)	1.00	Nos	767.00	767.00	INR Seven Hundred & Sixty Seven Only
95	Providing and laying SWR,PVC(Finolex or equivalent) pipe including cost of excavtion,C.C. etc including its jointing and connection all materials labour and T&P etc required for proper completion of work CSI No. 27.29 (a)	3.00	RM	287.00	861.00	INR Eight Hundred & Sixty One Only
96	Providing and laying SWR,PVC(Finolex or equivalent) pipe including cost of excavtion,C.C. etc including its jointing and connection all materials labour and T&P etc required for proper completion of work CSI No. 27.29 (c)	3.00	RM	397.00	1191.00	INR One Thousand One Hundred & Ninety One Only
97	Apply two coat Tapecrete mixed with White Cement and water to proper consistency on leaky surface including supply of all materials labour etc required for proper completion of work CSI No.28.16	15.00	sqm	116.00	1740.00	INR One Thousand Seven Hundred & Forty Only
98	Providing and applying plaster of Paris putty of 2 mm thickness over plastered surface to prepare the surface even the smooth complete. CSI No. 28.27	25.00	sqm	110.00	2750.00	INR Two Thousand Seven Hundred & Fifty Only
99	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test."All above operations to be done in order and as directed and specified by the Engineer-in-Charge : With average thickness of 120 mm and minimum thickness at khurra as 65 mm. CSI No. 28.28	30.00	Sqm	976.00	29280.00	INR Twenty Nine Thousand Two Hundred & Eighty Only
100	Supply and Fixing of 3 blade ceiling fan 1200 mm of Havells or equivalent including all material, T&P etc required for proper completion of work as approved by engineer in charge. CSI No. 28.39	2.00	Each	2894.00	5788.00	INR Five Thousand Seven Hundred & Eighty Eight Only

JE

S.D.O


E.E

101	Applying Two coat of Dr. Fixit pidicrete URP with cement slurry of one parts of Dr. Fixit pidicreteURP (covering are of URP 2.00 to 2.2Sqm/Kg) and 1.5 parts of cement on Horizontal and vertical damp surface. Before application, clean the surface with wire brush of scrubber to remove hidden dirt, loose particles, lattance and dust, degrese the surface by using suitable solvnet, thoroughly saturated the surface with potable water but at the time of application water should not be accumulated at any place as per direction E/I including supply of all materials, labours and T&P etc. required for proper completion of work. (SOR 2020-21)	80.00	sqm	159.00	12720.00	INR Twelve Thousand Seven Hundred & Twenty Only
102	Water Proofing coat with 3mm thick neat cement layer including 200 ml water Proofing Compound like as Dr. Fixit and other equivalent with all labour T&P . NSI	50.00	sqm	80.00	4000.00	INR Four Thousand Only
103	Finishing of walls with three coats water proof exterior emulsion paint "ACE" "Out Look" or equivalent make on new work including one priming coat (1 Liter paint diluted including 0.75 liter of water) to give an even shade complete including cost of all materials, labour and T&P etc. as per direction of E/I. NSI	125.00	sqm	76.50	9562.50	INR Nine Thousand Five Hundred & Sixty Two and Paise Fifty Only
104	Wiring point for light with 1.5 sq. mm. FR PVC insulated multistrand single copper conductor cable in PVC conduit pipe concealed in the wall, 14 SWG copper PVC coated Earth continuity wire, and approved quality, piano type switch ceiling rose/angle/batten holder as per approved sample on 3mm thick phenolic laminated bakelite sheet etc. of matching shade with wall colour complete in all respect. UP PWD SOR 2016 131 (C)	6.00	Nos	518.00	3108.00	INR Three Thousand One Hundred & Eight Only
105	Wiring point for fan/fresh air fan (light duty exhaust fan) 1.5 sq. mm FR PVC insulated multistrand single core copper conductor cable PVC conduit pipe concealed in the wall, 14 SWG copper earth continuity wire and approved quality, piano type switch & ceiling rose as per approved sample on 3mm thick phenolic laminated bakelite sheet etc. of matching shade with wall colour complete in all respects as per direction of E/I. UP PWD SOR 2016 133 (C)	3.00	Nos	595.00	1785.00	INR One Thousand Seven Hundred & Eighty Five Only
106	Wiring point for plug with 1.5 sq. mm FR PVC insulated multistrand single core copper conductor cable in PVC conduit pipe concealed in the wall 14 SWG copper earth continuity wire and approved quality type switch and socket as per approved sample etc. of matching shade with wall colour complete in all respects as per direction of E/I UP PWD SOR 2016 134 (C)	4.00	Nos	275.00	1100.00	INR One Thousand One Hundred Only
107	Supply and fixing of power plug with 15A/240V V flush type switch and 5 pin 15A/250V flush type universal socket in suitable M.S. box of 175mmx 100mmx50mm size with phenolic laminated bakelite sheet cover 3mm thick fixed with brass machine screw and cup washer. UP PWD SOR 2016 1139	5.00	Nos	270.00	1350.00	INR One Thousand Three Hundred & Fifty Only
108	Supply and wiring of submain with two numbers 4 sq. mm FR PVC insulated 1100 V grade multistrand single core copper conductor cable in 25 mm dia heavy duty (2 mm thick) PVC conduit concealed in wall complete with 1 number 2.5 Sq. mm FR PVC insulated multistrand copper conductor cable as earth continuity wire etc. complete in all respects. UP PWD SOR 2016 211 C	15.00	RM	150.00	2250.00	INR Two Thousand Two Hundred & Fifty Only
109	Supply and fixing 6A to 32A SP MCB C curve- 10 KA UP PWD SOR 2016 1002 C	1.00	Nos	105.00	105.00	INR One Hundred & Five Only
110	S/F 63 amp. S.P. Isolator of approved make and as per sample approved by E/I. UPPWD SOR 2016 1004(B)	1.00	Nos	150.00	150.00	INR One Hundred & Fifty Only
111	S/F surface/flush mounting 8 ways SPN distribution board without MCB complete in all respect as per direction of E/I UPPWD SOR 2016 1024 (B)	1.00	Nos	1430.00	1430.00	INR One Thousand Four Hundred & Thirty Only
Total in Figures					374715.85	INR Three Lakh Seventy Four Thousand Seven Hundred & Fifteen and Paise Eighty Five Only
Quoted Rate in Figures					Select	0.00 INR Zero Only
Quoted Rate in Words					INR Zero Only	


J.E


SDO


E.E


S.E