

Item Rate Book

Validate Print Help

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (UP)

Name of Work: विद्युत नगरीय विद्युत खाद-द्वितीय, गाजियाबाद के कोरीव में बिज विहार व सूर्यनगर पुलिस पर सेतु निर्माण में बाक 33 की सं 11 की लार्ज को पूर्ण जमा योजना में बाहर एजेसी के माध्यम से शिफ्ट कराना व अन्य कार्य।

Contract No: 0120 2607114

PRICE SCHEDULE FOR E-TENDER NO-08/W/2024-25/EUDD-2/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only ) GST EXTRA as applicable

NUMBER	TEXT #	QUANTITY	UNITS	TEXT #	BASIC RATE IN FIGURES TO BE ENTERED BY THE BIDDER IN INR / OTHER CURRENCY	TOTAL AMOUNT WITHOUT TAXES	TOTAL AMOUNT IN WORDS
Sl. No.	Item Description						
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय विद्युत खाद-द्वितीय, गाजियाबाद के कोरीव में बिज विहार व सूर्यनगर पुलिस पर सेतु निर्माण में बाक 33 की एवं 11 की लार्जों को पूर्ण जमा योजना में बाहर एजेसी के माध्यम से शिफ्ट कराना व अन्य कार्य।						
1.01	Safe Carriage of HT 11 KV XLPE Cable 3x185 Sq.mm from P.V.V.N.L. Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	4800	Mtr.	INR		0.00	INR Zero Only
1.02	Safe Carriage of Steel Tubular Pole 11 Meter from P.V.V.N.L. Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	26	No.	INR		0.00	INR Zero Only
1.03	Safe Carriage of line accessories such as 39 No. 33 KV PIN Insulator 39 No. Pin with Nut, 78 No. 33 KV Disc Fittings for Dog Conductor, 80 Meter G.I. Pipe 6" dia, 312 No. 11 KV Disc Insulator 8x5 Type from P.V.V.N.L. Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
1.04	Safe Carriage of 11 KV XLPE Outdoor Cable Box 3x185 Sq.mm from P.V.V.N.L. Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side and work of filling/insalation the same as per RESPO.	40	No.	INR		0.00	INR Zero Only
1.05	Laying of 11 KV HT Cable of 3x185 Sq.mm with Trenchless method by providing of HDPE Pipe Bore 160 mm dia and proper completion of work as per requirement of site.	4000	Mtr.	INR		0.00	INR Zero Only
1.06	Earthing of Pole as per RESPO specification.	26	No.	INR		0.00	INR Zero Only
1.07	Providing and Fixing of MS Angle Iron 65x55x3 mm bracing with 4 clamps.	13	Set	INR		0.00	INR Zero Only
1.08	Providing and Fixing of Top Channel 125x65 mm, 3200 mm with Clamp.	13	No.	INR		0.00	INR Zero Only
1.09	Providing and fixing of Stone Pad 300x300x75 mm.	26	No.	INR		0.00	INR Zero Only
2.00	Providing and Fixing of Earth Wire Clamp with Bolt & Nut.	13	No.	INR		0.00	INR Zero Only
2.01	Providing and Fixing of PG Clamp for Dog Conductor.	156	No.	INR		0.00	INR Zero Only
2.02	Providing and Fixing of Number Plate.	13	No.	INR		0.00	INR Zero Only
2.03	Providing and Fixing of Danger Board with Clamp.	13	No.	INR		0.00	INR Zero Only
2.04	Providing and Fixing of Barbe Wire.	52	Kg.	INR		0.00	INR Zero Only
2.05	Providing and Fixing of Aluminium Tape.	13	Kg.	INR		0.00	INR Zero Only
2.06	Providing and Fixing of Aluminium Paint.	26	Ltr.	INR		0.00	INR Zero Only
2.07	Providing and Fixing of Red Oxide Paint.	26	Ltr.	INR		0.00	INR Zero Only
2.08	Providing and Fixing of Stay Set Complete.	104	No.	INR		0.00	INR Zero Only
2.09	Providing and Fixing of F Brackets.	39	No.	INR		0.00	INR Zero Only
3.00	Correcting of Support.	26	No.	INR		0.00	INR Zero Only
3.01	Concreting of Stay.	104	No.	INR		0.00	INR Zero Only
3.02	PROVIDING and FIXING of Nutt & Bolts with Washer.	39	Kg.	INR		0.00	INR Zero Only
3.03	Carriage of old & used material from site to Store Sahibabad/ Ghaziabad including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words						0.00	INR Zero Only