

Validate

Print

Help

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Item Rate Book

Name of Work: विद्युत नगरीय बिजली मादहन-द्वितीय, गाजियाबाद के कार्यक्षेत्र में बिजली वान 2025-26 मर में 11 कोधी लाईन निर्माण एवं बाइफरकेशन करि के कर्य।

Contract No: 919320600

PRICE SCHEDULE FOR E-TENDER NO-13/W/2025-26/EUDC-2/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable

Sl. No.	Item Description	NUMBE	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #
		y	Units	Quoted Currency in INR / Other Currency	BASIC RATE in Figures To be entered by the Bidder	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	विद्युत नगरीय बिजली मादहन-द्वितीय, गाजियाबाद के कार्यक्षेत्र में बिजली वान 2025-26 मर में 11 कोधी लाईन निर्माण एवं बाइफरकेशन करि के कर्य। Qty. Vary as per site requirement ± 10%.	3	4	5	6	7	8
1.00							
1.01	Safe Carriage of 11 Mtrs. Long PCC Pole from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	117	No.	INR		0.00	INR Zero Only
1.02	Safe Carriage of 8.5 Mtrs. Long PCC Pole from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	6	No.	INR		0.00	INR Zero Only
1.03	Safe Carriage of 11 KV HT Cable 3x185 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	18224	Mtr.	INR		0.00	INR Zero Only
1.04	Safe Carriage of 4324 meter ACSR Dog Conductor. PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	4324	Mtr.	INR		0.00	INR Zero Only
1.05	Carriage of material such as 339 No. 11 KV Composite Polymeric Pin Insulator, 189 No. Disc Insulator with fittings from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only
1.06	Safe Carriage of 11 KV Outgoing VCB 400/200/5 from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	2	No.	INR		0.00	INR Zero Only
1.07	Erection of Double Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	12	No.	INR		0.00	INR Zero Only
1.08	Erection of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	93	No.	INR		0.00	INR Zero Only
1.09	Work of Concreting/Grouting of Pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	117	No.	INR		0.00	INR Zero Only
2.00	Laying/Erection of ACSR Dog Conductor on Pole. Proper completion of work as per requirement of site.	4324	Mtr.	INR		0.00	INR Zero Only
2.01	Laying of 11 KV HT Cable of 3x185 Sq.mm with Trenchless method in HDPE Pipe and proper completion of work as per requirement of site.	11610	Mtr.	INR		0.00	INR Zero Only
2.02	Normal Laying of 11 KV HT Cable of 3x185 Sq.mm. digging with Sand & Brick Proper completion of work as per requirement of site.	3842	Mtr.	INR		0.00	INR Zero Only
2.03	Normal Laying of 11 KV HT Cable of 3x185 Sq.mm. on Riser. Proper completion of work as per requirement of site.	2772	Mtr.	INR		0.00	INR Zero Only
2.04	Earthing of pole by providing Earth Rod (2540x20mm)	81	No.	INR		0.00	INR Zero Only
2.05	PROVIDING HDPE Pipe PE-80, NP-6, DN-140 Sq.mm dia Pipe.	11610	Mtr.	INR		0.00	INR Zero Only
2.06	PROVIDING AND FIXING 11 KV V-Type Steel Cross Arm.	50	No.	INR		0.00	INR Zero Only
2.07	PROVIDING AND FIXING MS Channel 100x50x5 MM.	328	Kg.	INR		0.00	INR Zero Only
2.08	PROVIDING AND FIXING MS Top Channel 100x50x6 MM 3200mm.	11	No.	INR		0.00	INR Zero Only
2.09	PROVIDING AND FIXING MS Dropper Channel 100x50x6 MM 2400mm.	145	No.	INR		0.00	INR Zero Only
3.00	PROVIDING AND FIXING Danger Board with Clamp for 11 KV	44	No.	INR		0.00	INR Zero Only
3.01	PROVIDING AND FIXING Number Plate with Clamp for 11 KV	23	No.	INR		0.00	INR Zero Only
3.02	PROVIDING AND FIXING Stay Set Complete.	10	No.	INR		0.00	INR Zero Only

3.03	PROVIDING AND FIXING LUG for ACSR Dog Conductor.	177	No.	INR		0.00	INR Zero Only
3.04	PROVIDING AND FIXING G.I. Barbed Wire 6 SWG.	73	Kg.	INR		0.00	INR Zero Only
3.05	PROVIDING AND FIXING Nut & Bolt with washer off Size as per RESPO.	414	Kg.	INR		0.00	INR Zero Only
3.06	PROVIDING AND FIXING F-Clamps with Nut & Bolts.	50	No.	INR		0.00	INR Zero Only
3.07	PROVIDING AND FIXING LT T-OFF Clamps with Nut & Bolts.	32	No.	INR		0.00	INR Zero Only
3.08	PROVIDING AND FIXING V-Type Steel Cross Arm Clamps for PCC with Nut & Bolts.	18	No.	INR		0.00	INR Zero Only
3.09	PROVIDING AND FIXING Bracing Set 4.3x4.3 Mtr. Angle Iron 65x65x6 mm with holding clamp	3	No.	INR		0.00	INR Zero Only
4.00	PROVIDING AND FIXING Stone Pad.	83	No.	INR		0.00	INR Zero Only
4.01	PROVIDING AND FIXING Cable Route Marker.	48	No.	INR		0.00	INR Zero Only
4.02	PROVIDING AND FIXING GI Pipe 150mm.	414	No.	INR		0.00	INR Zero Only
4.03	PROVIDING AND FIXING Holding Clamp for GI Pipe 150mm.	62	No.	INR		0.00	INR Zero Only
4.04	PROVIDING AND FIXING MS Holding Clamp for PCC Pole 11 Mtr.	179	No.	INR		0.00	INR Zero Only
4.05	PROVIDING AND FIXING MS Holding Clamp for Cable 3x185 Sq.mm.	178	No.	INR		0.00	INR Zero Only
4.06	PROVIDING AND FIXING PG Clamp for Dog to Dog	6	No.	INR		0.00	INR Zero Only
4.07	PROVIDING AND FIXING 11 KV Outdoor Cable Box 3x185 Sq.mm.	102	No.	INR		0.00	INR Zero Only
4.08	PROVIDING AND FIXING Straight Through jointing kit both of size 3x185 Sq.mm.	50	No.	INR		0.00	INR Zero Only
4.09	Road Restoration Charges as per Nagar Nilgam (Pakka Road) Aprox.	1500	Mtr.	INR		0.00	INR Zero Only
5.00	Road Restoration Charges as per Nagar Nilgam (Kachha Road) Aprox.	3000	No.	INR		0.00	INR Zero Only
5.01	Dismantling/Remaining unused Material of material from site and carriage to store.	1	Job	INR		0.00	INR Zero Only
Total in Figures		INR Zero Only					
Quoted Rate in Words		INR Zero Only					