

Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Work: बिजुल सार्वजनिक बिजुल सार्वजनिक-वितीय, गाजियाबाद के कार्यालय में बिजुल सार्वजनिक 2025-26 मद्र में एलटीडी लाईन के जर्जर तार बदलना एवं सुरक्षाका का काई।

Contract No: 9193320600

# Item Rate Book

## PRICE SCHEDULE FOR E-TENDER NO-17/M/2025-26/EUDC-2/GZB

(This BOC template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only ) GST EXTRA as applicable

Sl. No.	Item Description	Quantit y	Units	Quoted Currency In INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	बिजुल सार्वजनिक बिजुल सार्वजनिक-वितीय, गाजियाबाद के कार्यालय में बिजुल सार्वजनिक 2025-26 मद्र में एलटीडी लाईन के जर्जर तार बदलना एवं सुरक्षाका का काई। Qty. Vary as per site requirement $\pm$ 10%.						
1.01	Safe Carriage of 11 Mtrs. Long PCC Pole from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	13	No.	INR		0.00	INR Zero Only
1.02	Safe Carriage of 9 Mtrs. Long PCC Pole from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	20	No.	INR		0.00	INR Zero Only
1.03	Safe Carriage of 8.5 Mtrs. Long PCC Pole from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	369	No.	INR		0.00	INR Zero Only
1.04	Safe Carriage of 7500 meter ACSR Dog Conductor. PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	7500	Mtr.	INR		0.00	INR Zero Only
1.05	Safe Carriage of 3000 meter ACSR Rabbit Conductor for Neutral. PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	3000	Mtr.	INR		0.00	INR Zero Only
1.06	Safe Carriage of 12239 meter ABC (3x120+1x19+1x16 Sq.mm) Cable from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	12239	Mtr.	INR		0.00	INR Zero Only
1.07	Safe Carriage of 850 meter XPLE 3x120 Sq.mm Cable from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	850	Mtr.	INR		0.00	INR Zero Only
1.08	Safe Carriage of 2400 meter LT XPLE 1x400 Sq.mm Cable from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	2400	Mtr.	INR		0.00	INR Zero Only
1.09	Safe Carriage of materials 20 No. D.O. Fuse Set, 40 No. TPWO & 210 No. 3 Phase Distribution Box from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
2.00	Erection of Double Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	20	No.	INR		0.00	INR Zero Only
2.01	Erection of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	362	No.	INR		0.00	INR Zero Only
2.02	Work of Concreting/GROUTING of Pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	402	No.	INR		0.00	INR Zero Only
2.03	Laying/Erection of ACSR Dog Conductor on Pole. Proper completion of work as per requirement of site.	7500	Mtr.	INR		0.00	INR Zero Only
2.04	Laying/Erection of ACSR Rabbit Conductor on Pole. Proper completion of work as per requirement of site.	3000	Mtr.	INR		0.00	INR Zero Only
2.05	Laying/Erection of 11 KV HT Cable of 1x400 Sq.mm. Proper completion of work as per requirement of site.	2400	Mtr.	INR		0.00	INR Zero Only
2.06	Laying/Erection of ABC (3x120+1x19+1x16 Sq.mm) Cable on pole. Proper completion of work as per requirement of site.	12239	Mtr.	INR		0.00	INR Zero Only
2.07	Laying/Erection of 11 KV HT Cable of 3x120 Sq.mm. Cable. Proper completion of work as per requirement of site.	850	Mtr.	INR		0.00	INR Zero Only
2.08	Earthing of pole by providing Earth Rod (25x40x20mm)	402	No.	INR		0.00	INR Zero Only
2.09	PROVIDING AND FIXING Spacer LT PVC.	66	No.	INR		0.00	INR Zero Only
3.00	PROVIDING AND FIXING Aluminium Binding Wire. 6 mm	12	Kg.	INR		0.00	INR Zero Only

3.02	PROVIDING AND FIXING MS Top Channel 125x65x1300 MM (T-Off)	3	No.	INR			0.00	INR Zero Only
3.03	PROVIDING AND FIXING MS Dropper Channel 100x50x2028 MM.	70	No.	INR			0.00	INR Zero Only
3.04	PROVIDING AND FIXING LT Shackle Strip with Nut & Bolt for LT Section Pole	4	Kg.	INR			0.00	INR Zero Only
3.05	PROVIDING AND FIXING LT Shackle Insulator. 100x115mm	36	No.	INR			0.00	INR Zero Only
3.06	PROVIDING AND FIXING Extra for Stay at Angle location (Stay Rod 16x1800mm Stay wire 5 Kg., Stay Clamp, Bolt & Nut with Grouting).	10	Kg.	INR			0.00	INR Zero Only
3.07	PROVIDING AND FIXING AL. LUG of 400 Sq.mm	19	No.	INR			0.00	INR Zero Only
3.08	PROVIDING AND FIXING Nut & Bolt with washer off Size as per RESPO.	160	No.	INR			0.00	INR Zero Only
3.09	PROVIDING AND FIXING LT Piercing connector (120 Sq.mm)	330	Kg.	INR			0.00	INR Zero Only
4.00	PROVIDING AND FIXING Three Phase Distribution Clamp	841	No.	INR			0.00	INR Zero Only
4.01	PROVIDING AND FIXING Holding Clamps for Pole	226	No.	INR			0.00	INR Zero Only
4.02	PROVIDING AND FIXING LT Clamp for PCC with Nut & Bolt	840	No.	INR			0.00	INR Zero Only
4.03	PROVIDING AND FIXING Stone Pad.	447	No.	INR			0.00	INR Zero Only
4.04	PROVIDING AND FIXING Suspension Clamp with I-Hook	283	No.	INR			0.00	INR Zero Only
4.05	PROVIDING AND FIXING Dead End Clamp with I-Hook	320	No.	INR			0.00	INR Zero Only
4.06	PROVIDING AND FIXING G.I. Wire 8 SWG	216	No.	INR			0.00	INR Zero Only
4.07	PROVIDING AND FIXING Connecting Lead 1x16 Sq.mm	80	Kg.	INR			0.00	INR Zero Only
4.08	PROVIDING AND FIXING Connecting Lead 1x35 Sq.mm	501	Mtr.	INR			0.00	INR Zero Only
4.09	PROVIDING AND FIXING Earthing Wire Clamp with Nut & Bolt	208	No.	INR			0.00	INR Zero Only
5.00	Construction of plinth of size 2MX2MX1.5M above ground level and one ft. below the ground level of 9" width by first class brick in ratio 1:4 of cement and sand shall be provided and rammering will be done properly after that a retaining wall of 9" width by first class brick in ratio 1:4 of cement and sand shall be made. The earth shall be filled upto one ft. below the top of the plinth. After this brick ballast shall be provided upto 6" from the earth level and proper rammering shall be done. One no. jaal of 12mm MS Tor shall be fixed in the hollow of the plinth and one ft. thick RCC in 1:2:4 ratio of cement, sand and stone ballast shall be laid on the top of the plinth. The 12mm thick plastering shall be done all around the plinth in ratio 1:4 ratio of cement and sand. The contractor shall be responsible to complete the work as per direction of supervising Engineer. It includes the cost of labour, T&P, carrier etc. required for proper completion of the work (This material will be provided by the Contractor).	75	No.	INR			0.00	INR Zero Only
5.01	Fabrication of wire mesh fencing frames of different size fabricate out of MS angle iron of size 3x3x2M. Each frame duly welded and fixing with wire mesh of size 25x25x10 SWG hot dipped galvanized within the frame pressed under MS flats of size 40x5mm inside the angle on all four side with help of approx. 20No. Bolts & Nuts of 10mm diameter 45cm legs of frame will be grouted in 1:2:4 cement coarse sand and 20mm gauge stone blast in the size of 0.22x0.22x0.45meter. Each will be painted with one coat of red oxide and two coat of Aluminium paint of approved mark after proper cleaning. Fixing of wire mesh fencing around on plinth of T/F with wire gauge 25x5mm, MS Angle 35x35x5mm with gate.	63	No.	INR			0.00	INR Zero Only
5.02	REPAIRING OF DAMAGED PLINTH AS PER SITE REQUIREMENT.	125	No.	INR			0.00	INR Zero Only
5.03	REPAIRING OF DAMAGED FENCING AS PER SITE REQUIREMENT.	137	No.	INR			0.00	INR Zero Only
5.04	DISMANTLING OF OLD AND DAMAGED STP.	157	No.	INR			0.00	INR Zero Only
5.05	DISMANTLING OF OLD AND DAMAGED ACSR DOGWEASEL CONDUCTOR.	16000	Mtr.	INR			0.00	INR Zero Only
5.06	CARRIAGE OF OLD AND DAMAGED POLE FROM SITE OF WORK TO PVVL STORE. LOADING AND UNLOADING AT BOTH ENDS.	157	No.	INR			0.00	INR Zero Only
5.07	CARRIAGE OF OLD AND DAMAGED ACSR DOGWEASEL SCRAP FROM SITE OF WORK TO PVVL STORE. LOADING AND UNLOADING AT BOTH ENDS.	16000	Mtr.	INR			0.00	INR Zero Only
Total in Figures								
Quoted Rate in Words								
							INR Zero Only	