

# Item Rate BoQ

Validate Print Help

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण खण्ड-बटन, से-10, बसुवरा, गण्डियाबाद के कार्केत्र में गणेशपुर पुलिया से सर्वोदय पब्लिक स्कूल तक नाले की रिटर्निंग वॉल का निर्माण में अवरोधक 11 कोणीय एल्स्टीक विद्युत लार्जिन सिस्टिम कादि कार्य ई-निविदा द्वारा बाह्य एजेन्सी के माध्यम से कराने हेतु।

Contract No: 9193320605

PRICE SCHEDULE FOR E-TENDER NO-22W/2025-26/D-6/EUDC-2/GZB														
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only ) GST EXTRA as applicable														
Sl. No.	TEXT #	Item Description	NUMBER #	TEXT #	Units	TEXT #	Quoted Currency in INR / Other Currency	NUMBER #	BASIC RATE In Figures To be entered by the Bidder Rs. P	NUMBER #	TOTAL AMOUNT Without Taxes	NUMBER #	TOTAL AMOUNT In Words	TEXT #
1		2	3	4		5		6		7		8		
1.00		विद्युत नगरीय वितरण खण्ड-बटन, गण्डियाबाद के कार्केत्र में गणेशपुर पुलिया से सर्वोदय पब्लिक स्कूल तक नाले की रिटर्निंग वॉल का निर्माण में अवरोधक 11 कोणीय एल्स्टीक विद्युत लार्जिन सिस्टिम कादि कार्य ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने हेतु।												
1.01		Safe Cartage of 11 Mtrs. Long ST Pole from PNVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	8	No.		INR				0.00	INR Zero Only			
1.02		Safe Cartage of 11 Mtrs. Long PCC Pole from PNVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	14	No.		INR				0.00	INR Zero Only			
1.03		Safe Cartage of 8.5 Mtrs. Long PCC Pole from PNVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	9	No.		INR				0.00	INR Zero Only			
1.04		Carriage of 11 KV XLPE Cable 3x185 Sq.mm. from PNVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	490	Mtr.		INR				0.00	INR Zero Only			
1.05		Carriage of ABC (3X120+1X95+1X16) Sq.mm. from PNVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	260	Mtr.		INR				0.00	INR Zero Only			
1.06		Carriage of ACSR DOG Conductor from Store Centre, Sahibabad/Ghaziabad/Noida to site of work and Laying, stringing, binding, jumpering & sagging in 3 phase including loading & unloading at both ends.	750	Mtr.		INR				0.00	INR Zero Only			
1.07		Carriage of materials 21 No.11 KV Pin Insulator, 4 No. Cable Box O/D 11 KV 3X185 XLPE, 07 No. 11 KV V-Type Steel Cross Arm from PNVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at	1	Job.		INR				0.00	INR Zero Only			
1.08		Work of Concreting/Grouting of Pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	31	No.		INR				0.00	INR Zero Only			
1.09		Erection of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	31	No.		INR				0.00	INR Zero Only			
2.00		Laying/Erection of 11 KV HT Cable of 3x185 Sq.mm. on Riser. Proper completion of work as per requirement of site.	490	Mtr.		INR				0.00	INR Zero Only			

2.01	Laying/Erection of ABC (3X120+1X95+1X16) Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	260	Mtr.	INR		0.00	INR Zero Only
2.02	Earthing of pole by providing Earth Rod (2540x20mm)	17	No.	INR		0.00	INR Zero Only
2.03	Providing & Fixing Three Phase Distribution Box RESPO Drawing.	7	No.	INR		0.00	INR Zero Only
2.04	Providing & Fixing Nut & Bolt of off Size as per RESPO Drawing.	20	Kg.	INR		0.00	INR Zero Only
2.05	Providing & Fixing Stone Pad as per RESPO Norms.	17	No.	INR		0.00	INR Zero Only
2.06	Providing & Fixing LT Piercing Connector For 120/35 mm. as per RESPO Drawing.	21	No.	INR		0.00	INR Zero Only
2.07	Providing & Fixing Stay Clamps 16X1800 as per RESPO Drawing.	2	No.	INR		0.00	INR Zero Only
2.08	Providing & Fixing Cable Box ST. TH 11 KV 3X185 as per RESPO Drawing.	2	No.	INR		0.00	INR Zero Only
2.09	Providing & Fixing Holding Clamps as per RESPO Drawing.	44	No.	INR		0.00	INR Zero Only
3.00	Providing & Fixing Suspension Clamps with EYEHOOK as per RESPO Drawing.	10	No.	INR		0.00	INR Zero Only
3.01	Providing & Fixing Channel 100x50mm. as per RESPO Drawing.	300	Kg.	INR		0.00	INR Zero Only
3.02	Providing & Fixing Top Channel 100x50x2240mm. as per RESPO Drawing.	1	No.	INR		0.00	INR Zero Only
3.03	Providing & Fixing Dropper Channel 100x50x2028mm. as per RESPO Drawing.	3	No.	INR		0.00	INR Zero Only
3.04	200 kg. Steel Melttable Scrap, Dismantling of Old/Damaged Scrap of 50 Kg. ACSR DOG Conductor Scrap and carriage to JE Store/Store Centre Sahibabad/ Ghaziabad/ Noida including loading and unloading at both ends.	1	Job.	INR		0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	<b>INR Zero Only</b>
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					