

Item Rate BoQ

Validate

Print

Help

Tender Inviting Authority: Superintending Engineer (Com & Tech), EUDC, Ghaziabad (U.P)

Name of Work: गाजियाबाद क्षेत्र-पूर्वीय, गाजियाबाद के अन्तर्गत विद्युत सार्वजनिक वितरण खण्ड-11 कोवैरो एवं एलसीटी नेटवर्क, साहिबाबाद, गाजियाबाद के वसुधारा, कोयाम्बी, इन्दिरापुरम, खोड़ा इत्यादि कार्यक्षेत्रों में 33 कोवैरो एवं 11 कोवैरो के मूनिपल कोरिलों में प्रतिस्थापना टीक/सम्मत करने का कार्य वित्तीय वर्ष 2025-28 एवं 2028-29।

Contract No: 9193320600

Name of the Bidder/Bidding	
----------------------------	--

PRICE SCHEDULE FOR E-TENDER NO-04/WI/2025-26/D-11KVSBD/EUDC/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable

NUMBER	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #	TEXT #
1	2	3	4	5	6	7	8		
1.00	Locating and repairing of faults occurred in 33 KV & 11 KV underground cables including digging upto cable, cutting the faulty part of cable, repairing etc and other related works to make Cable healthy (Cable fault locating machine mounted on a vehicle with Experienced Technicians, Driver and helpers & other required Infrastructure will be provided by the Contractor).								
1.01	33 KV cable fault Location by fault locator machine.	278	No.	INR		0.00	INR Zero Only		
1.02	Providing and Fixing of 33 KV Jointing kit for making joints (33 KV 3x300/400 sqmm. PVVNL Approved make will be Provided by the contractor).	200	No.	INR		0.00	INR Zero Only		
1.03	Fixing of 33 KV Jointing kit for making joints for filling (33 KV 3x300/400 sqmm. Provided by the Department).	78	No.	INR		0.00	INR Zero Only		
1.04	11 KV cable fault location by fault locator machine.	312	No.	INR		0.00	INR Zero Only		
1.05	Providing and Fixing of 11 KV Jointing kit for making joints (11 KV 3x125 sqmm. PVVNL Approved make will be Provided by the contractor).	250	No.	INR		0.00	INR Zero Only		
1.06	Fixing of 11 KV Jointing kit for making joints (11 KV 3x125 sqmm. Provided by the Department).	62	No.	INR		0.00	INR Zero Only		
1.07	For repairing of cable fault digging trench of suitable size up to 2meter of depth or as per site requirement for making joints by cutter/digging machine may be used at fault site.	590	Job.	INR		0.00	INR Zero Only		
1.08	High pressure testing of cable to remove moisture in cable.	150	No.	INR		0.00	INR Zero Only		
1.09	Replacement of 33 KV of damaged cable (cable shall be provided by the Department).	139	No.	INR		0.00	INR Zero Only		
2.00	Replacement of 11 KV of damaged cable (cable shall be provided by the Department).	156	No.	INR		0.00	INR Zero Only		
Total in Figures						0.00	INR Zero Only		
Quoted Rate in Words							INR Zero Only		