

Inviting Authority: Superintending Engineer Electricity Civil Distribution Circle, PUVNL, Meerut.

Name of Work: Roof Treatment and other Miscellaneous civil repair works at 33/11 K.V. Sub-Station Butrada Distt.-Shamli.

T.S. No: 22/ECDC/MRT/2021-22

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
1	Excavation in foundation in ordinary soil (loam, clay or sand) including lift upto 1.5 Metre and lead upto 30 metre including filling, watering, and ramming of excavated earth into the trenches or into the space between the building and the side of the foundation or in to the plinth and removal & disposal of surplus earth as directed by the E/I up to a distance of 30m from the foundation trenches. CSI No. 4.01	0.50	Cum	172.00	86.00	INR Eighty Six Only
2	Earth filling under floors and/or substation area including cost of the earth when obtained from within 8 km Outside UPPCL area including its royalty and Carriage including watering, ramming in 20cm thick layers and dressing of earth etc. All complete. CSI No. 4.10	1.00	Cum	414.00	414.00	INR Four Hundred & Fourteen Only
3	Concrete with 4cm gauge stone ballast, coarse sand (F.M. 1.8 to 2.5) & cement in proportion of 12:6:1 in foundations & under floors including supply of all materials, labour and tools and plants etc. required for proper completion. CSI No. 5.02	0.10	Cum	4971.00	497.10	INR Four Hundred & Ninety Seven and Paise Ten Only
4	Cement concrete with 2cm gauge approved hard stone ballast, coarse sand (F.M. 1.8 to 2.5) and cement in proportion of 4:2:1 including supply of all materials, labour, side shuttering if required and T&P etc. required for proper completion of work. CSI No. 5.06	0.20	Cum	6520.00	1304.00	INR One Thousand Three Hundred & Four Only
5	Concreting of 40 mm RCC Trench cover in mild steel Frame work with RCC 1:1.5:3 Cement, Coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast with 3 mm thick Floating coat of neat Cement finish on top of cover complete with all labour, materials and placing the same in proper position at required location of Cable Trench within the Substation area. CSI No. 5.18	1.00	sqm	326.00	326.00	INR Three Hundred & Twenty Six Only
6	Cement concrete with 2cm gauge approved hard stone ballast, coarse sand (F.M. 1.8 to 2.5) and cement in proportion of 3:1.5:1 including supply of all materials, labour, side shuttering if required and T&P etc. required for proper completion of work. CSI No. 5.21	0.10	Cum	6955.00	695.50	INR Six Hundred & Ninety Five and Paise Fifty Only
7	Precast cement concrete door sills, chauthats boundary posts, shelves and similar small work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast in the proportion 1:1.5:3, excluding reinforcement but including fixing the same in position including cost of all other material, labor and T&P. CSI No. 5.22	0.20	Cum	8405.00	1681.00	INR One Thousand Six Hundred & Eighty One Only
8	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Daila, Jhansi or other quarries in proportion 1:1.5:3 in lintels of doors and windows, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.23	0.10	Cum	8058.00	805.80	INR Eight Hundred & Five and Paise Eighty Only
9	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in Slab, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.24	0.10	Cum	9275.00	927.50	INR Nine Hundred & Twenty Seven and Paise Fifty Only
10	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in Lighter Beam i.e. having span upto 6.0 M excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.25	0.20	Cum	10037.00	2007.40	INR Two Thousand & Seven and Paise Forty Only
11	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in raft foundation and footings excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.27	0.20	Cum	7671.00	1534.20	INR One Thousand Five Hundred & Thirty Four and Paise Twenty Only
12	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc in proportion 1:1.5:3 in RCC T-Beam slab and column excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.29	0.20	Cum	10189.00	2037.80	INR Two Thousand & Thirty Seven and Paise Eighty Only

J.E.

300

EE

AE

	1st class brick (not less than class 150) work in 1:6 C.M. with cement and coarse sand (2.9 to 3.2 F.M) mortar in foundation and plinth including supply of all material, labour and T&P etc. required for proper completion of work. CSI No. 6.01	0.20	Cum	4518.00	903.60	INR Nine Hundred & Three and Paise Sixty Only
14	1st class brick work in 1:6 C.M. with cement and coarse sand of 2.25 F.M. mortar in super structure including necessary cutting and moulding of brick as required including honey comb brick work, thickness of wall one brick (230mm) thick in super structure. CSI No. 6.01+6.08	1.00	Cum	4820.00	4820.00	INR Four Thousand Eight Hundred & Twenty Only
15	Same as item no. 14 above but for wall of half brick 4.5" (115 mm) thick but in 1:6 C.M. with cement and coarse sand of 2.25 F.M. mortar. CSI No. 6.01+6.09	0.10	Cum	4971.00	497.10	INR Four Hundred & Ninety Seven and Paise Ten Only
16	First class brick laid dry in foundation and Plinth as in Circular soakpit wall of one brick thickness and 2.0 to 3.0 M depth including cutting moulding bricks as required including cost of all other materials labour and T&P Complete. CSI No. 6.16	0.10	Cum	4085.00	408.50	INR Four Hundred & Eight and Paise Fifty Only
17	Brick work in foundation & plinth with old dismantled bricks (supplied by department free of cost) and coarse sand of F.M. 1.8 to 2.5 mortar in 1:6 including supply of all other materials, labour, removing mortar & cleaning of old & used bricks, T&P etc complete. CSI No. 6.18	0.10	Cum	2572.00	257.20	INR Two Hundred & Fifty Seven and Paise Twenty Only
18	Removal of cement mortar from dismantled bricks and stacking in countable position at place as directed by Engineer in charge including cost of all materials labour and T&P required for proper completion of work. CSI No. 6.22	1.00	%o	1230.00	1230.00	INR One Thousand Two Hundred & Thirty Only
19	Supply and filling brick bat in soak pit including all material, labour and T&P etc complete. (01 soak pit) CSI No. 6.23	1.00	Cum	1251.00	1251.00	INR One Thousand Two Hundred & Fifty One Only
20	25mm.thick Damp proof course with cement concrete consisting of 1 part cement, 1½ parts approved coarse sand and 3 parts approved 12 mm graded stone grit and also including liquid water proofing material as approved Engineer-in-charge in proportion as specified by the manufacturer. CSI No. 7.02	2.00	Sqm	314.00	628.00	INR Six Hundred & Twenty Eight Only
21	Supply and fixing of 32 mm thick single leaf flush door shutter (boiled water resistance, phenol maldehyde resin bonded, hot pressed factory made) commercial quality to I.S.2202 part-1 (1983) ISI marked including fixing of wooden cleats and stoppers and including fixing and adjustment of hinges, bolts, locks, handles, springs and other fittings but excluding their supply including all materials, labour & T&P etc. required for proper completion of work. CSI No. 8.57	0.10	Sqm	1915.00	191.50	INR One Hundred & Ninety One and Paise Fifty Only
22	Mild Steel or Iron work in heavy sizes such as trusses built up gates, door frames, record, racks roof work gates etc. wrought to required form including holes rivetting or welding where necessary and also fixing in proper position and alignment including cost of all materials supplied by contractor. CSI No. 9.01	0.010	M.T.	83076.00	830.76	INR Eight Hundred & Thirty and Paise Seventy Six Only
23	TMT/Tor steel in plain work such as reinforced concrete or reinforced brick work (when not included in an over all rates) wrought to required shape as necessary including bending for proper completion of the work and including supply of steel its wastage, bend, hooks and authorized overlapping shall be measured. (Steel shall be arranged by the contractor). CSI No. 9.03	0.010	M.T.	74620.00	746.20	INR Seven Hundred & Forty Six and Paise Twenty Only
24	Supply and fixing galvanised mosquito proof jali (16x24 gauge) with M.S. flat of 20 x 3 mm. size, on both sides screwed or welded to window or door frame. CSI No. 9.18	12.00	Sqm	632.00	7584.00	INR Seven Thousand Five Hundred & Eighty Four Only
25	12 mm thick plaster with cement mortar consisting of one part of cement & four part of coarse sand (1:4), minimum thickness not to be less than 10 mm including supply of all material, labour and T&P etc for proper completion of work. CSI No. 11.07	35.00	Sqm	178.00	6230.00	INR Six Thousand Two Hundred & Thirty Only
26	Same as item No. 25 above but with 1:6 cement and coarse sand mortar. CSI No. 11.09	20.00	Sqm	169.00	3380.00	INR Three Thousand Three Hundred & Eighty Only
27	Add for extra labour to all items of plaster if done in ceiling. CSI No. 11.10	2.00	Sqm	21.40	42.80	INR Forty Two and Paise Eighty Only
28	Add for extra labour and Materials for plaster over rough face of one brick thick wall. CSI No. 11.12	2.00	Sqm	24.00	48.00	INR Forty Eight Only
29	2 cm (3/4") thick cement plaster in dado or skirting in 1:2 C.M. consisting of one part of cement and two parts of approved coarse sand laid in panels finished with 3mm (1/8") thick floating coat of neat cement or cement and marble dust in ratio of 5:1 including supply of all materials, labour and T&P etc. required for proper completion of the work CSI No. 11.13	2.00	Sqm	260.00	520.00	INR Five Hundred & Twenty Only
30	Smixing approved water proofing compound (CICO, DR FIXIT etc) in cement mortar in plaster or concrete work in the proportion as recommended by the manufacturer. CSI No. 11.15	2.00	Kg	47.00	94.00	INR Ninety Four Only
31	Providing (12x15) mm section groove in plaster including all material, labour and T&P etc. required for proper completion of the work. CSI No. 11.16	2.00	RM	12.00	24.00	INR Twenty Four Only
32	Making drip course (25x12) mm in 1:2 cement and coarse sand including supply of all materials, labour and T&P etc required for proper completion of work. CSI No. 11.19	52.00	RM	11.00	572.00	INR Five Hundred & Seventy Two Only

J.E.

Recht
S.D.O.

EE

	mm thick floating coat of neat cement finish including supply of all materials, labour and T&P etc. required for proper completion of the work. (cement consumption 0.044 bag/Sq.m.) CSI No. 11.20	2.00	Sqm	19.00	38.00	INR Thirty Eight Only
34	40 cm thick 1:2:4 plain cement concrete floor with cement, approved coarse sand & 2cm graded approved stone ballast laid in panels finished with 3mm floating coat of neat cement or cement and marble dust in ratio of 5:1 as specified and removing any overlapping mortar at the joints of the panels if any and giving them a uniform finish including supply of all materials, labour and T&P etc. required for proper completion of the work. without base CC. CSI No. 12.04	1.00	Sqm	386.00	386.00	INR Three Hundred & Eighty Six Only
35	First class bricks on Edge floor laid dry, joints sand filled, including preparation base to proper slope and its ramming including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 12.07	1.00	Sqm	496.00	496.00	INR Four Hundred & Ninety Six Only
36	Supply and Laying 8 mm thick glazed floor tiles of Somany, Johnson or equivalent make, laid with 1:3 cement and approved coarse sand mortar finished with white cement slurry, jointing and polishing complete, including supply of all materials, labour and T&P etc. completion required for proper completion of the work. CSI No. 12.11	1.00	Sqm	1056.00	1056.00	INR One Thousand & Fifty Six Only
37	Providing and fixing glass strips of 3.15 mm thickness & 40mm depth in joints of floor and skirting at the time of laying floors, flush with floor level including supply of all materials, labour & T&P etc. required for proper completion of work. CSI No. 12.14	1.00	RM	31.00	31.00	INR Thirty One Only
38	Providing and laying 18 mm. thick Kota stone in flooring or skirting over base cement mortar 1:4 mix and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing complete and including supply of all materials labour and T&P etc required for proper completion of the work. CSI No. 12.17	0.50	Sqm	1114.00	557.00	INR Five Hundred & Fifty Seven Only
39	Supply of 80 mm thick I shaped mechanically compressed inter locking cement concrete paver block manufactured by high pressure & controlled vibration machine having plan dimension 200X(160+120 mm) with minimum 5 mm thick topping of O.P. Cement mixed with 25% marble powder. The compressive strength of concrete pavers blocks shall not be less than 30 MPa & 4.5 Kg/No. including cost of all material, labour, T&P etc. required for proper completion of work as directed by Engineer-in-charge but excluding G.S.T. which shall be paid extra as per rules. CSI No. 12.23	1.00	Sqm	974.00	974.00	INR Nine Hundred & Seventy Four Only
40	Painting or varnishing new iron work in small areas or new wood work with one coat of ready mixed priming paint and one coat of approved superior quality ready mix paint "Luxol" or equivalent brand or varnish including supply of all materials, labour and T&P etc. required for proper completion of the work. Paint to be used should conform to the I.S. 103-1950. CSI No. 13.01	5.00	Sqm	71.00	355.00	INR Three Hundred & Fifty Five Only
41	Same as item No.40 above but for every coat after 1st coat. CSI No. 13.02	75.00	Sqm	35.00	2625.00	INR Two Thousand Six Hundred & Twenty Five
42	Same as item no. 40 above but every coat on previously painted old wood or steel work. CSI No. 13.03	71.00	Sqm	47.00	3337.00	INR Three Thousand Three Hundred & Thirty Seven Only
43	Removing Paint or varnish with paint remover or with caustic soda including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 13.07	2.00	Sqm	81.00	162.00	INR One Hundred & Sixty Two Only
44	One priming coat and one coat oil bound distemper on new work including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 13.08	2.00	Sqm	65.00	130.00	INR One Hundred & Thirty Only
45	Same as item No. 44 above but for every coat after the first coat. CSI No. 13.09	505.00	Sqm	27.00	13635.00	INR Thirteen Thousand Six Hundred & Thirty Five Only
46	Same as item No.44 above but for every coat on previously old distempered surface. CSI No. 13.10	505.00	Sqm	33.00	16665.00	INR Sixteen Thousand Six Hundred & Sixty Five Only
47	Applying Birla or equivalent putty on new interior or exterior surface over one coat of water based cement primer of ICI or equivalent brand for smoothening and levelling of the surface as per requirement and direction of Engineer I/C including cost of all material, labour, T & P etc required for proper completion of work. CSI No. 13.20	55.00	Sqm	84.00	4620.00	INR Four Thousand Six Hundred & Twenty Only
48	Applying BIRLA PUTTY or equivalent putty on previously bila putty smoothen surface over one coat of water base cement primer of ICI or equivalent brand for smoothening and leveling of the surface as per requirement and direction of E/I including cost of all material, labour and T&P required for proper completion of work. CSI No. 13.21	90.00	Sqm	41.00	3690.00	INR Three Thousand Six Hundred & Ninety Only
49	Painting one coat with APEX or equivalent brand weather coat paint on new wall surfaces (well prepared with Birla putty and one coat of primer ICI or equivalent which shall be paid separately) including through washing with water including cost of all materials, labour, T&P required for proper completion of work. CSI No. 13.22	2.00	Sqm	90.00	180.00	INR One Hundred & Eighty Only
50	Same as in item no 49 above but for every coat of additional APEX or equivalent brand weather coat paint. CSI No. 13.23	2.00	Sqm	41.00	82.00	INR Eighty Two Only
51	Same as in item no 49 above but for every coat of additional APEX or equivalent brand weather coat paint coat paint previously treated surface. CSI No. 13.24	2.00	Sqm	62.00	124.00	INR One Hundred & Twenty Four Only

J.E.

S.D.O.

EE

	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by the Engineer-in-charge within a distance of 60 metres. CSI No. 15.01	1.80	Cum	505.00	909.00	INR Nine Hundred & Nine Only
53	Dismantling reinforced cement concrete or reinforced brick work, including stacking of dismantled materials as directed by the Engineer-In-charge within a distance of 60 metres. CSI No. 15.03	12.00	Cum	1128.00	13536.00	INR Thirteen Thousand Five Hundred & Thirty Six Only
54	Dismantling cement concrete or brick or granolithic floors including base concrete and including stacking of dismantled materials as directed by the Engineer In-charge within a distance of 60 metres. CSI No. 15.05	2.00	Sqm	58.00	116.00	INR One Hundred & Sixteen Only
55	Dismantling doors and windows chowkhats including stacking of materials as directed by Engg-in-Charge within a distance of 60 metres. CSI No. 15.10	2.00	Sqm	69.00	138.00	INR One Hundred & Thirty Eight Only
56	Dismantling existing plaster including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.11	40.00	Sqm	41.00	1640.00	INR One Thousand Six Hundred & Forty Only
57	Scrapping old white or colour wash or distemper including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.12	650.00	Sqm	13.00	8450.00	INR Eight Thousand Four Hundred & Fifty Only
58	Dismantling of existing pale / security / Chain link fencing including post and stacking property as directed by the Engineer-I/C including cost of all materials, labour, T&P required for proper completion of work. CSI No. 15.13	2.00	RM	126.00	252.00	INR Two Hundred & Fifty Two Only
59	Dismantling of existing damaged Mud Faska over the roof Cleaning the surface with wire brush, removal and disposal of rubbish at a distance 100 meters also including the cost of cleaning and stacking of usable materials etc. including cost of all materials, labour, T&P required for proper completion of work. CSI No. 15.14	1.00	Sqm	139.00	139.00	INR One Hundred & Thirty Nine Only
60	Renewing panes of 4.8 to 5.7 mm glass including supply of glass with putty and brads including supply of all materials, labour and t&P etc. required for proper completion of the work. (a) glass of 4 mm thick. CSI No. 20.04 (b)	4.00	Sqm	836.00	3344.00	INR Three Thousand Three Hundred & Forty Four Only
61	Cleaning of Septic tank including disposal of wastage out side the UPPCL area as per directed by the Engineer-I/C including cost of all materials, labour, T&P required for proper completion of work CSI No. 20.12	1.00	Nos	1667.00	1667.00	INR One Thousand Six Hundred & Sixty Seven Only
62	Disposal of Rubbish / debris out side the UPPCL area directed by the Engineer-I/C including cartage labour, and materials, T&P required for proper completion of work. (no deduction for voids shall be made) CSI No. 20.16	2.00	cum	330.00	660.00	INR Six Hundred & Sixty Only
63	Supply and replacing of following chromium polished iron fittings including cost of nuts, bolts etc. complete. (a) L drops 16 mm dia x 300 long CSI No. 20.17 (a)	3.00	Nos	187.00	561.00	INR Five Hundred & Sixty One Only
64	Same as item No.63 above but for (c) Tower bolts 10 mm dia x 100 mm long. CSI No. 20.17 (c)	3.00	Nos	64.00	192.00	INR One Hundred & Ninety Two Only
65	Same as item No. 63 above but for (d) Iron hinges 100 mm size. 12 gauge. thick. CSI No. 20.17 (d)	5.00	Nos	77.00	385.00	INR Three Hundred & Eighty Five Only
66	Same as item No.63 above but for (f) M.S. handles 100 mm size. CSI No. 20.17 (f)	3.00	Nos	39.00	117.00	INR One Hundred & Seventeen Only
67	Laying chicken mesh of (20 mm) hexagonal heavy quality over roofs of joints of roof as per direction Engineer-in-charge. CSI No. 20.21	3.00	Sqm	80.00	240.00	INR Two Hundred & Forty Only
68	Wiring point for light with 1.5 sq. mm. FR PVC insulated multistrand single copper conductor cable in PVC conduit pipe concealed in the wall, 14 SWG copper PVC coated Earth continuity wire, and approved quality, piano type switch ceiling rose/angle/batten holder as per approved sample on 3mm thick phenolic laminated bakelite sheet etc. of matching shade with wall colour complete in all respect. UP PWD SOR 2016 131 (C)	2.00	Nos	518.00	1036.00	INR One Thousand & Thirty Six Only
69	Wiring point for fan/fresh air fan (light duty exhaust fan) 1.5 sq. mm FR PVC insulated multistrand single core copper conductor cable PVC conduit pipe concealed in the wall, 14 SWG copper earth continuity wire and approved quality, piano type switch & ceiling rose as per approved sample on 3mm thick phenolic laminated bakelite sheet etc. of matching shade with wall colour complete in all respects as per direction of E/I. UP PWD SOR 2016 133 (C)	1.00	Nos	595.00	595.00	INR Five Hundred & Ninety Five Only
70	Wiring point for plug with 1.5 sq. mm FR PVC insulated multistrand single core copper conductor cable in PVC conduit pipe concealed in the wall 14 SWG copper earth continuity wire and approved quality type switch and socket as per approved sample etc. of matching shade with wall colour complete in all respects as per direction of E/I UP PWD SOR 2016 134 (C)	1.00	Nos	275.00	275.00	INR Two Hundred & Seventy Five Only
71	Supply and fixing of power plug with 15A/240V V flush type switch and 5 pin 15A/250V flush type universal socket in suitable M.S. box of 175mmx 100mmx50mm size with phenolic laminated bakelite sheet cover 3mm. thick fixed with brass machine screw and cup washer. UP PWD SOR 2016 1139	1.00	Nos	270.00	270.00	INR Two Hundred & Seventy Only

J.E.

S.D.O.

EE


	Providing and fixing 15 mm dia B-class Jindal, JTC, ISI marked G.I. pipes complete with special such as bend, tee, socket, cross, clamp etc earth work including filling the trenches etc required for proper completion of the work. the rate also includes concealed GI fitting where required, cutting and making good the walls etc and all materials, labour and T&P complete. CSI No. 26.01 (a)	2.00	RM	190.00	380.00	INR Three Hundred & Eighty Only
73	Same as item No.72 but for 20 mm dia. CSI No. 26.01 (b)	2.00	RM	226.00	452.00	INR Four Hundred & Fifty Two Only
74	Same as item No. 72 but for 32 mm dia. CSI No. 26.01 (d)	2.00	RM	364.00	728.00	INR Seven Hundred & Twenty Eight Only
75	Providing and fixing 15 mm dia Jindal, JTC, ISI marked G.I. pipes complete with special such as bend, tee, socket, cross, clamp etc earth work including filling the trenches etc required for proper completion of the work. the rate also includes external GI fitting where required, cutting and making good the walls etc and all materials, labour and T&P complete. CSI No. 26.02 (a)	2.00	RM	163.00	326.00	INR Three Hundred & Twenty Six Only
76	Same as Item No. 75 but for 20 mm dia. CSI No. 26.02 (b)	2.00	RM	194.00	388.00	INR Three Hundred & Eighty Eight Only
77	Same as Item No. 75 but for 32 mm dia. CSI No. 26.02 (d)	2.00	RM	312.00	624.00	INR Six Hundred & Twenty Four Only
78	Supply and fixing of Syntex or equivalent make water storage tank including all materials, labours, T&P etc required for proper completion of work. CSI No. 26.12	500.00	Ltr	11.00	5500.00	INR Five Thousand Five Hundred Only
79	Supply and fixing 15 mm dia C/PVC bib cock including replacing of old bib cock complete. CSI No. 26.13 (c)	1.00	Nos	61.00	61.00	INR Sixty One Only
80	Providing and fixing CP BRASS BIB COCK 15 mm dia. HEAVY QUALITY (400gm) (L & K and equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P. required for proper completion of work. CSI No. 26.16 (a)	2.00	Nos	660.00	1320.00	INR One Thousand Three Hundred & Twenty Only
81	Providing and fixing CP BRASS STOP COCK 15 mm dia. HEAVY QUALITY (400gm) (L & K and equi.) fittings, ISI mark heavy quality including supply of all materials, labour and T&P required for proper completion of work. CSI No. 26.16 (c)	2.00	Nos	660.00	1320.00	INR One Thousand Three Hundred & Twenty Only
82	Same as item No. 81 CP BRASS Angle Valve HEAVY QUALITY (L&K or equi.). CSI No. 26.16 (l)	2.00	Nos	571.00	1142.00	INR One Thousand One Hundred & Forty Two Only
83	Same as item No. 81 CONCEALED STOP COCK HEAVY QUALITY (L&K or equi.). CSI No. 26.16 (k)	2.00	Nos	800.00	1600.00	INR One Thousand Six Hundred Only
84	Providing and fixing of 110 mm dia PVC pipe 6 Kg/ Sq.cm for with special such as Tee, bend, socket, elbow etc including supply of all labour, material, T & P etc complete required for proper completion of work. CSI No. 26.17	2.00	RM	257.00	514.00	INR Five Hundred & Fourteen Only
85	Providing and fixing first quality white glazed "Orissa" pattern W.C.Pan Hindustan, Cera make. size 580 mm (Hindustan, Cera Make) with out "P" trap including supply of all materials, labour and T&P etc. complete. CSI No. 27.01	1.00	Nos	2354.00	2354.00	INR Two Thousand Three Hundred & Fifty Four Only
86	Providing and fixing 510X400 mm wash hand basin of white glazed earthen ware first quality I.S.I. marked (Hindustan, Neycer / Cera make) including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.09	1.00	Nos	3056.00	3056.00	INR Three Thousand & Fifty Six Only
87	Providing and Fixing 10 Liters low level PVC flushing cistern, COMPLETE WITH ALL FITTINGS including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.12	1.00	Nos	1320.00	1320.00	INR One Thousand Three Hundred & Twenty Only
88	Providing and fixing 600 mm x 450 mm beveled edge mirror of Atul, Kiran make glass with Indian polish 6.50 mm thick complete with back of 600 mm x 450 mm x 6 mm hard board sheet fixed to wooden cleats with C.P. brass screws and washers including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.15	1.00	Nos	962.00	962.00	INR Nine Hundred & Sixty Two Only
89	Providing and fixing 750 mm x 20 mm size C.P. brass towel rail of approved quality including brackets including supply of all materials, labour and T&P etc. required for proper completion of the work and cutting and making good the wall plaster etc. required for work. CSI No. 27.16	1.00	Nos	609.00	609.00	INR Six Hundred & Nine Only
90	Providing and fixing soap dish chromium plated with brackets fixed to wooden cleats with brass screws including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.19	1.00	Nos	265.00	265.00	INR Two Hundred & Sixty Five Only
91	Supply and fixing CP Nahani Trap India make of heavy approved quality complete with CI grating, including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 27.21 (a)	1.00	Nos	761.00	761.00	INR Seven Hundred & Sixty One Only
92	Providing and applying plaster of Paris putty of 2 mm thickness over plastered surface to prepare the surface even the smooth complete. CSI No. 28.27	60.00	Sqm	106.00	6360.00	INR Six Thousand Three Hundred & Sixty Only


JE

Rockit
S.D.O.


EE

	<p>providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:4 (1 cement : 4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:4 (1 cement : 4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement : 4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be done in order and as directed and specified by the Engineer-in-Charge : With average thickness of 120 mm and minimum thickness at khurra as 65 mm.</p> <p>CSI No. 28.28</p>	166.00	Sqm	932.00	154712.00	INR One Lakh Fifty Four Thousand Seven Hundred & Twelve Only
94	Supply and Fixing of 3 blade ceiling fan 1200 mm of Havells or equivalent including all material, T&P etc required for proper completion of work as approved by engineer in charge.	2.00	Each	3994.00	7988.00	INR Seven Thousand Nine Hundred & Eighty Eight Only
95	Water Proofing coat with 3mm thick neat cement layer including 200 ml water Proofing Compound like as Dr. Fixit and other equivalent with all labour T&P .	2.00	sqm	80.00	160.00	INR One Hundred & Sixty Only
96	Finishing of walls with three coats water proof exterior emulsion paint "ACE" "Out Look" or equivalent make on new work including one priming coat (1 Liter paint diluted including 0.75 liter of water) to give an even shade complete including cost of all materials, labour and T&P etc. as per direction of E/I.	241.00	sqm	76.50	18436.50	INR Eighteen Thousand Four Hundred & Thirty Six and Paise Fifty Only
97	Supply and wiring of submain with two numbers 4 sq. mm FR PVC insulated 1100 V grade multistand single core copper conductor cable in 25 mm dia heavy duty (2 mm thick) PVC conduit concealed in wall complete with 1 number 2.5 Sq. mm FR PVC insulated multistand copper conductor cable as earth continuity wire etc. complete in all respects.	2.00	RM	150.00	300.00	INR Three Hundred Only
98	Supply and fixing 6A to 32A SP MCB C curve- 10 KA	1.00	Nos	105.00	105.00	INR One Hundred & Five Only
99	S/F 63 amp. S.P. Isolator of approved make and as per sample approved by E/I.	1.00	Nos	150.00	150.00	INR One Hundred & Fifty Only
100	S/F surface/flush mounting 8 ways SPN distribution board without MCB complete in all respect as per direction of E/I	1.00	Nos	1430.00	1430.00	INR One Thousand Four Hundred & Thirty Only
Total in Figures					339563.46	INR Three Lakh Thirty Nine Thousand Five Hundred & Sixty Three and Paise Forty Six Only
Quoted Rate in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	


J.E.G.)


SDO(C)


EEC(C)


Afzal